

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

ADDENDUM NO. 4

PROJECT NO. 43-18-05 (PART A)
BRIDGE REPAIR AND REHABILITATION
OHIO TURNPIKE RAMP OVER OHIO TURNPIKE (EXIT 218), M.P. 218.7
MAHONING COUNTY, OHIO

PROJECT NO. 43-18-05 (PART B)
BRIDGE REPLACEMENT
OHIO TURNPIKE OVER MILL CREEK BIKEWAY, M.P. 223.0
MAHONING COUNTY, OHIO

OPENING DATE:

PREVIOUSLY EXTENDED TO 2:00 P.M. (EASTERN TIME), JUNE 1, 2018

ATTENTION OF BIDDERS IS DIRECTED TO:
QUESTIONS RECEIVED THROUGH 12PM ON MAY 29, 2018
-ANDPROJECT NO. 43-18-05A: PLAN SHEET NO. 2 OF 18

Issued by the Ohio Turnpike and Infrastructure Commission on May 29, 2018 by Anthony D. Yacobucci, Chief Engineer, and Mark R. Musson, Director of Contracts Administration.

Anthony D. Yacobucci

Date

Mark R. Musson

Date

ANSWERS TO QUESTIONS RECEIVED THROUGH 12PM ON MAY 29, 2018:

- Q#39 The cover sheet for part A "Index of Sheets" indicates a General Summary sheet 2. This sheet is missing from the plans.
- A#39 The Commission provides the missing Plan Sheet No. 2 of 18 from Project No. 43-18-05A, which was inadvertently excluded from the set issued through BidExpress, with this Addendum No. 4

Receipt of Addendum No. 4 Project No. 43-18-05 (PART A & B) is hereby acknowledge	d:
(Firm Name)	
(Signature)	
(Printed Name)	
(Date)	

GENERAL SUMMARY							
ITEM	TOTAL	UNIT	DESCRIPTION	MP 218.7	AS PER PLAN, SHEET NO.		
			PART A AND PART B - GENERAL (REFERENCE NUMBERS 1 - 5)				
IB.ART.6	LUMP	LUMP SUM	PREMIUM FOR CONTRACT PERFORMANCE BOND AND PAYMENT BOND	LUMP			
SP 614	LUMP	LUMP SUM	MAINTAINING TRAFFIC	LUMP			
SP 619	LUMP	LUMP SUM	FIELD OFFICE	LUMP			
SP 623	LUMP	LUMP SUM	CONSTRUCTION LAYOUT SURVEY	LUMP			
624	LUMP	LUMP SUM	MOBILIZATION	LUMP			
			ROADWAY				
614	4	EACH	REPLACEMENT SIGN	4	3		
630	16	SQ. FT.	SIGNING MISC.; ADDITIONAL SIGNS, GROUND MOUNTED, AS DIRECTED BY THE ENGINEER	16	3		
642	0.2	MILE	YELLOW EDGE LINE, 6", TYPE 1	0.2			
642	0.2	MILE	WHITE EDGE LINE, 6", TYPE 1	0.2			
642	0.2	MILE	WHITE LANE LINE, 6", TYPE 1	0.2			
			STRUCTURE				
SP 202	LUMP	LUMP SUM	PORTIONS OF STRUCTURE REMOVED	LUMP			
SP 509	100	POUND	EPOXY COATED REINFORCING STEEL, GRADE 60 (**)	100			
513	10	EACH	WELDED STUD SHEAR CONNECTORS, AS PER PLAN (**)	10	10/18		
SP 516A	30	FOOT	CRACK REPAIR USING EPOXY INJECTION (**)	30			
SP 516B	1,745	FOOT	SEALING OF CONSTRUCTION JOINTS	1,745			
SP 519	120	SQ. FT.	PATCHING CONCRETE STRUCTURES	120			
SP 527	LUMP	LUMP SUM	FALSEWORK, TEMPORARY BRACING, AND PROTECTIVE STRUCTURES	LUMP			
SP 536	745	SQ. YD.	CONCRETE WEATHERPROOFING, BARRIERS AND PARAPETS	745			
SP 536	2,223	SQ. YD.	CONCRETE WEATHERPROOFING, DECK, ABUTMENT SLABS AND APPROACH SLABS	2,223			
848	1,434	SQ. YD.	MICRO-SILICA MODIFIED CONCRETE OVERLAY USING HYDRODEMOLITION, 2" THICK	1,434			
848	1,434	SQ. YD.	SURFACE PREPARATION USING HYDRODEMOLITION	1,434			
848	40	CU. YD.	MICRO-SILICA MODIFIED CONCRETE OVERLAY (VARIABLE THICKNESS), MATERIAL ONLY	40			
848	4	CU. YD.	TEST SLAB	4			
848	18	CU. YD.	FULL DEPTH REPAIR	18			
848	9	SQ. YD.	HAND CHIPPING	9			

NOTES:
1. FOR GENERAL NOTES, SEE SHEET 10 OF 18.

SPECIFIC STRUCTURE REHABILITATION SCOPE OF WORK IS SHOWN ON THE GENERAL PLAN AND PROFILE SHEET FOR EACH STRUCTURE.

3. (**) DESIGNATES A CONTINGENCY QUANTITY, TO BE USED AT THE DIRECTION OF THE ENGINEER.



PROJECT 43-18-05A

DATE:

GENERAL SUMMARY

TURNPIKE

OHIO

COMMIS

0