OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION

ADDENDUM NO. 1
ISSUED: MAY 27, 2022

PROJECT NO. 53-22-02

REPAIRS AND RESURFACING GREAT LAKES & TOWPATH SERVICE PLAZAS MILEPOST 170.10, CUYAHOGA COUNTY, OHIO

ISSUED MAY 12, 2022

OPENING DATE: 2:00 P.M.(EASTERN TIME) JUNE 2, 2022

ATTENTION OF BIDDERS IS DIRECTED TO:

ANSWERS TO QUESTIONS RECEIVED THROUGH 5:00 P.M. ON MAY 26, 2022

MODIFICATIONS TO THE CONTRACT DOCUMENTS

Plan Sheets: 2, 4, and 5
-AND-
Bid Schedule of Items and Estimated Quantities Worksheet
Reference No. 2

Issued by the Ohio Turnpike and Infrastructure Commission through Aimee W. Lane, Esq., Director of Contracts Administration.

Aimee W. Lane

Aimee W. Lane, Esq.,
Director of Contracts Administration

May 27, 2022
Date

ANSWERS TO QUESTIONS RECEIVED THROUGH 5:00 P.M. ON MAY 26, 2022:

Q#1 Is a Material Transfer Device per SP 400 III.E.3.i required?

A#1 A Material Transfer Device, per SP 400.III.E.3.(i), is not required for this Project. The Commission will review the general rideability of the Work performed for the Project as called for in SP 400.III.I Tolerance of the Finished Surface.

Q#2 Is SP 400S – Smoothness of Pavement Surfaces applicable to this project?

A#2 SP 400S – Smoothness of Pavement Surfaces is applicable to this Project with the following modification(s):

- *A Class 1 inertial profilometer is not required for this Project.*
- *Final pavement surface will be evaluated in accordance with the SP 400S.C. Rolling Straight Edge Tolerances.*
- *Any corrective action required shall be in accordance with SP 400S.E. Corrective Action.*

Q#3 will we be required to do any temporary striping for the parking areas during construction?

A#3 Temporary striping for the parking areas will not be required.

Q#4 Can you please review/clarify the quantities provided on pages 4-5? Quantities on pages provided do not match bid quantities.

*A#4 Plan Sheet 4 and 5 of 11 have been reviewed and revised. Plan Sheet 4 of 11, the reference to ~~THE TOTAL ESTIMATED WORK AREA = 51,300 S.Y~~ has been deleted. Plan Note 3, the quantities of pavement planning have been revised from ~~1533~~ to **1550** and the quantity of SP 402 has been revised from ~~255~~ to **85**. Plan Sheet 5 of 11, the reference to ~~THE TOTAL ESTIMATED WORK AREA = 55,100 S.Y~~ has been deleted. Additionally, Plan Sheet 2 of 11 has been reviewed and revised due to changes on Plan Sheets 4 and 5 of 11. Plan Sheet 2 of 11, the quantity of Item 245, Pavement Planing, Asphalt Concrete (T=3") has been revised from ~~102,044.00~~ to **100,600.00.***

*Due to the changes on Plan Sheet 2, 4, and 5 of 11, the bid form has been reviewed and revised. The quantity for Reference No. 2, has been revised from ~~102,044.~~ to **100,600.** The revised bid form, Plan Sheets 2, 4, and 5 of 11 have been included with this Addendum No. 1.*

END OF ADDENDUM NO. 1