OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION

ADDENDUM NO. 1
ISSUED: MARCH 21, 2024

PROJECT NO. 43-24-03

BRIDGE DECK REPLACEMENT & BRIDE REMOVAL OHIO TURNPIKE OVER NORTH COAST INLAND TRAIL M.P. 83.3 OHIO TURNPIKE OVER WAGGONER RD (C.R. 82) M.P. 83.3 SANDUSKY COUNTY, OHIO

ISSUED MARCH 13, 2024

OPENING DATE: 2:00 P.M.(EASTERN TIME) APRIL 3, 2024

ATTENTION OF BIDDERS IS DIRECTED TO:

ANSWERS TO QUESTIONS RECEIVED THROUGH 2:00 P.M. ON MARCH 21, 2024

MODIFICATIONS TO THE CONTRACT DOCUMENTS

Original Construction and Rehabilitation Plans for Ohio Turnpike over N.C.I.T. and Waggoner Road, MP 83.3
(For Reference Only)

Issued by the Ohio Turnpike and Infrastructure Commission through Aimee W. Lane, Esq., Director of Contracts Administration.

Aimee W. Lane

Aimee W. Lane, Esq.,
Director of Contracts Administration

March 21, 2024
Date

ANSWERS TO QUESTIONS RECEIVED THROUGH 2:00 P.M. ON MARCH 21, 2024:

Q#1 Bid item 55- 12" Conduit, Type B: plan sheet 57 shows the 59' run crossing existing Waggoner Road at station 108+15 with a "PAVEMENT REPLACEMENT" note. Plan sheet 6 existing pavement detail for Waggoner Road says, "Thickness Unknown". How is the pavement replacement to be paid for as this bid item does not have an "As Per Plan" designation?

A#1 Payment for the pavement replacement for the 12-inch conduit installation is provided for on the Pavement Sub-summary, Sheet 35 of 110, under Waggoner Road Sta. 108+12.00 to Sta. 108 +18.00.

Q#2 Please provide the existing plans for the Ohio Turnpike Structure over North Coast Inland Trail and the Ohio Turnpike Structure over Waggoner Road.

A#2 Existing plans for the Ohio Turnpike over N.C.I.T. and over Waggoner Road have been included as part of this addendum.

Q#3 Bid item 58- 30" Conduit, Type B: plan sheet 56 shows the 71' run crossing existing Waggoner Road at around station 102+92 which is in a mill/fill typical section. Plan sheet 6 existing pavement detail for Waggoner Road says, "Thickness Unknown". How is the pavement replacement to be paid for as this bid item does not have an "As Per Plan" designation?

A#3 The pavement build-up over the 30-inch conduit shall match the "Buildup Detail 1" on the Typical Sections, Sheet 6 of 110. The cost for Item 304 – Aggregate Base (T=6") and Item 301 - 4"Asphalt Concrete Base, PG64-22 shall be included with the cost for Item 611 – 30" Conduit, Type A, 706.02.

END OF ADDENDUM NO. 1