



**OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION**

ADDENDUM NO. 2
ISSUED: MAY 23, 2023

PROJECT NO. 54-22-01(REBID)

**ERIE ISLANDS PUMP STATION AND FORCE MAIN ERIE ISLANDS SERVICE PLAZA
MILEPOST 100.00 SANDUSKY COUNTY, OHIO**

ISSUED MAY 2, 2023

OPENING DATE: 2:00 P.M. (EASTERN TIME) MAY 23 30, 2023

ATTENTION OF BIDDERS IS DIRECTED TO:

ANSWERS TO QUESTIONS RECEIVED THROUGH 12:00 P.M. ON MAY 23, 2023

MODIFICATIONS TO THE CONTRACT DOCUMENTS

Plan Sheets: 6, 36, 37, 38 of 43

-AND-

Bid Schedule of Items and Estimated Quantities Worksheet
Reference Nos.: 19, 20, and 21

Issued by the Ohio Turnpike and Infrastructure Commission through Aimee W. Lane, Esq., Director of Contracts Administration.

Aimee W. Lane

Aimee W. Lane, Esq.,
Director of Contracts Administration

May 23, 2023
Date

ANSWERS TO QUESTIONS RECEIVED THROUGH 12:00 P.M. ON MAY 23, 2023:

Q#1 The project plans sheets 36 and 37 show a 332' Jack and Bore under the turnpike overpass immediately followed by a 156' Directional Drill under the Pickerel Creek road culverts. We do not feel the case bore / directional drill are possible to complete as designed due to the limited space and depth of excavation for the connection pit between the two, as well its proximity to existing overpass foundations, existing culverts and power poles in this area. We feel a better installation would be an approximately 700' Directional Drill as shown on attached. This could be done per the project Directional Drilling spec with 6" PVC C900 Certa-Loc carrier pipe alone, or if a casing pipe is required, a HDPE or PVC casing could be used or a TR Flex Ductile Iron casing if more durability is desired. A case bore of this length would not be a suitable application of that form of installation due to the extended length.

Should this option be selected we would also request an extension of the bid time in order to compile our bid, as in its current form we do not feel the job can be completed and will not be completing a bid.

A#1 Plan Sheets 6, 36, 37, and 38 have been revised to reflect directional drilling for force main installation under the Ohio Turnpike. Reference Nos. 19, 20, and 21 have been updated on the Estimated Quantities Worksheet to reflect plan changes.

Note: The Bid Opening Date was previously extended from May 23, 2023, at 2:00 PM until May 30, 2023, at 2:00 PM.

END OF ADDENDUM NO. 2