OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION

ADDENDUM NO. 3
ISSUED: OCTOBER 6, 2023

PROJECT NO. 59-23-02

EXIT 34 RAMP RECONSTRUCTION MILEPOST 34.9 FULTON COUNTY, OHIO

ISSUED SEPTEMBER 14, 2023

OPENING DATE: 2:00 P.M. (EASTERN TIME) OCTOBER ~~5~~ *12*, 2023

ATTENTION OF BIDDERS IS DIRECTED TO:

ANSWERS TO QUESTIONS RECEIVED THROUGH 9:00 A.M. ON OCTOBER 6, 2023

MODIFICATIONS TO THE CONTRACT DOCUMENTS
Plan Sheets 7, 8 and 22 of 93
-AND-
Bid Schedule of Items and Estimated Quantities Worksheet Reference Nos. 63, 67, and 69 of 77

Issued by the Ohio Turnpike and Infrastructure Commission through Aimee W. Lane, Esq., Director of Contracts Administration.

Aimee W. Lane

Aimee W. Lane, Esq.,
Director of Contracts Administration

October 6, 2023
Date

ANSWERS TO QUESTIONS RECEIVED THROUGH 9:00 A.M. ON OCTOBER 6, 2023:

Q#7 The note for Item SP 622 – Portable Barrier on plan sheet 7 indicates the portable barrier shall be paid for as lump sum. Currently bid reference 67 is set up as a per Foot unit price item to pay for the portable barrier. Please clarify how Item SP 622 is to be paid. Additionally, if paid as a per Foot unit price item please review the bid quantity. Bid total is currently 9,188 Foot, while the MOT general summary total is 8,093 Foot.

*A#7 Plan Sheet 7, 8, and 22 of 93 have been reviewed and revised. The note on Plan Sheet 7 of 93 referencing Temporary Portable Barriers has been clarified to indicate that the barrier will be included in the cost of SP 622, Portable Barrier. For additional clarification, the note on Plan Sheet 8 of 93 for ITEM SP 622-PORTABLE BARRIER has been revised to show that the portable barrier will be paid for **per linear foot** and not paid for ~~as lump sum~~. Additionally, Plan Sheet 22 of 93, the quantity for Item SP 622, PORTABLE BARRIER (WITHOUT GLARE SCREEN) has been reviewed and revised from ~~9188~~ to **8093.** The Estimated Quantity Worksheet has been reviewed and revised. The quantity for Ref. No. 67. has been changed from ~~9188~~ to **8093**. Revised Plan Sheets 7, 8, and 22 of 93 and the revised Estimated Quantities Worksheet has been included as part of this Addendum.*

Q#9 Can you supply storm piping invert elevations for the proposed catch basins? Thank you.

*A#9 Contractor shall review Plan Sheet 6 of 93 containing plan note **DRAINAGE STRUCTURE FIELD VERIFICATION***. The plan note is also pictured below.

DRAINAGE STRUCTURE FIELD VERIFICATION:
EXISTING DEPTHS AND PIPE INVERTS OF STORM SEWER STRUCTURES TO BE REPLACED SHALL BE FIELD MEASURED BY THE CONTRACTOR.

PAYMENT FOR ALL OPERATIONS DESCRIBED ABOVE SHALL BE INCLUDED IN THE CONTRACT PRICE FOR THE PERTINENT 611 CONDUIT ITEMS.

Note: *Plan Sheet 22 of 93 has been reviewed and revised for various items. The total quantity for Item SP 614C, REMOVAL OF PAVEMENT MARKING, Ref. No 63, has been revised from ~~6.92~~ to **6.11**, the total quantity for Item 614, BUSINESS ENTRANCE SIGN, Ref. No. 66, has been revised from ~~2~~ to **1**, and the total quantity for Item 614, WORK ZONE EDGE LINES, CLASS 1, 6", 642 PAINT (WHITE), Ref. No. 69, has been revised from ~~1.79~~ to **1.58.** The Estimated Quantities Worksheet has been reviewed and revised as well. Item 614, BUSINESS ENTRANCE SIGN, Ref. No. 66, is correctly shown on the Estimated Quantities Worksheet. Revised Plan Sheet 22 of 93 and the revised Estimated Quantities Worksheet has been included as part of this Addendum.*

END OF ADDENDUM NO. 3