SHEET NUMBER 6A	17	18	19	20	21	21A	22	165	167	168	169	174	175	461	464	465	485	ITEM	GRAND TOTAL	UNIT	DESCRIPTION	REF. NO.
																					PAVEMENT	
	1000																	251	1,000	SQ YD	PARTIAL DEPTH PAVEMENT REPAIR	
	7200											1805						252	9,005	FT	FULL DEPTH PAVEMENT SAWING	
												1756						254	1,756	SQ YD	PAVEMENT PLANING, ASPHALT CONCRETE (T=1 1/4")	
												10693						254	10,693	SQ YD	PAVEMENT PLANING, ASPHALT CONCRETE (T=2")	
												28808						254	28,808	SQ YD	PAVEMENT PLANING, ASPHALT CONCRETE (T=3")	
	800																	SP 451	800	SQ YD	FULL DEPTH PAVEMENT REPAIR (ASPHALT)	
	800																	SP 451	800	SQ YD	FULL DEPTH PAVEMENT REPAIR (CONCRETE)	
												142411						SP 302	142,411	CU YD	ASPHALT CONCRETE BASE, PG 64-22	
												34915						SP 304	34,915	CU YD	AGGREGATE BASE (SHOULDER)	
												66400		156				SP 304	66,555	CU YD	AGGREGATE BASE	
					178	178												SP 304	356	CU YD	GRANULAR MATERIAL	
												8542						SP 402	8,542	CU YD	ASPHALT CONC. INTERMEDIATE COURSE OR RECYCLED ASPHALT CONC. INTERMEDIATE COURSE, PG64-22	
												13008						SP 402	13,008	CU YD	ASPHALT CONC. INTERMEDIATE COURSE OR RECYCLED ASPHALT CONC. INTERMEDIATE COURSE, PG76-22 (FR)	
												1400						SP 402	1,400	CU YD	ASPHALT CONCRETE INTERMEDIATE COURSE USING CRUSHED STONE, PG76-22 (FR)	
												61						SP 404	61	CU YD	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC ON CROSSOVERS, PG64-22 , (1 1/4" AVE.)	
												8098						SP 404	8,098	CU YD	ASPHALT CONCRETE SURFACE COURSE, USING CRUSHED STONE, PG64-22	
												12190						SP 404	12,190	CU YD	ASPHALT CONCRETE SURFACE COURSE, USING CRUSHED SLAG, PG76-22 (FR)	
												195155						SP 404A	195,155	FT	JOINT SEALER	
												81125						407	81,125	GALLON	NON-TRACKING TACK COAT	
														935				452	935	SQYD	15-1/4" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC1, AS PER PLAN	
								318										609	318	FT	CURB, TYPE 4-C	
		5798																617	5,798	SQ YD	SHOULDER PREPARATION	
		36																617	36	MGAL	WATER	
		483																SP 617	483	CU YD	COMPACTED AGGREGATE	
		71										640						SP 627	711	CU YD	STONE SHOULDER PROTECTION (WITH GUARDRAIL)	
		2																SPECIAL	2	EACH	CONSTRUCT NEW CROSSOVER WITH 12' SHOULDER	18
											1	31.17						SPECIAL	31.17	MILE	SONIC NAP ALERT PATTERN (SNAP)	
																			1			
																					WATER WORK	
																		680	1	LUMP	WATER WELL ASSEMBLY	481
																					SANITARY SEWER	
																		680	1	LUMP	COMPLETE WASTE TREATMENT SYSTEM	480
																					MAINTENANCE OF TRAFFIC	
																					FOR MAINTENANCE OF TRAFFIC GENERAL SUMMARY SEE SHEET	29
																					LIGHTING	
																					FOR LIGHTING GENERAL SUMMARY SEE SHEET	491
																					TRAFFIC CONTROL	
																					FOR TRAFFIC CONTROL GENERAL SUMMARY SEE SHEET	505
																					BRIDGE MAINTENANCE	
																					FOR BRIDGE MAINTENANCE SUMMARIES SEE SHEET	583
																					GENERAL	
																		IB, ART.6	1	LUMP	PREMIUM FOR CONTRACT PERFORMANCE BOND AND PAYMENT BOND	
																		SP 614	1	LUMP	MAINTAINING TRAFFIC	
																		SP 619	1	LUMP	FIELD OFFICE	
																		SP 623	1	LUMP	CONSTRUCTION LAYOUT SURVEY	
																		624	1	LUMP	MOBILIZATION	

DESIGN AGENCY: GPD GROUP® 520 South Main Street, Suite 2531 Akron, OH, Columbus, Toledo & Cleveland, Inc. 330.572.2100 Fax: 330.572.2101

NO.	REVISIONS	BY	DATE
1	ADDENDUM #4	PJF	8/25/20
-	-	-	-
-	-	-	-

DESIGNED CLH | CHECKED LRK | DRAWN CLH | IN CHARGE MRG

GENERAL SUMMARY

WILLIAMS COUNTY

M.P. 0.0 TO M.P. 7.2

PROJECT 39-20-01A

DATE: 06/26/20

3 / 3

163 / 613

OHIO TURNPIKE

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

O:\2018\2018161\roadway\sheets\2018161GG001.dwg; Sheet 3; 8/25/20 - 9:09am