ESTIMATED QUANTITIES

CARRIED TO GENERAL SUMMARY ON SHEET 162

ITEM	TOTAL	UNIT	DESCRIPTION
202	200	FT.	PIPE REMOVED, OVER 24" (2)
202	2	EACH	HEADWALL REMOVED
601	4.89	CU. YD.	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER
SP 611	1	EACH	MANHOLE, NO. 3, AS PER PLAN
SP 611	345	FT.	48" CONDUIT, TYPE A, 706.02
SPECIAL	2	EACH	48" PRECAST CONCRETE END SECTION
503	1	LUMP	COFFERDAMS AND EXCAVATION BRACING (CULVERT #2)

O:\2018\2018161\drainage\sheets\2018161DC001.dwg, 48 CMP @ MP 3.52, 8/24/20 - 2:23pm

DESIGN AGENCY
GPD GROUP®
Gruen Associates
Gannett Fleming
DESIGN GROUP, Inc.
520 South Main Street, Suite 2531
Akron, Ohio 44311
330.572.2100 Fax: 330.572.2101

NO.	REVISIONS	BY	DATE
1	ADDENDUM #3	PJF	8/19/20
2	ADDENDUM #4	PJF	8/24/20
-			
-			

DESIGNED LRK
DRAWN LRK
CHECKED PJF
IN CHARGE MRG

CULVERT DETAIL
CULVERT #2 - STA. 193+98.73
M.P. 3.52

PROJECT 39-20-01A
DATE: 06/26/20

2 / 8

465 / 613

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION