SECTION A–A

SECTION B–B

SECTION C–C

SECTION D–D

SECTION E–E

NOTE:

ALL PREFORMED JOINT MATERIAL AND SEALER SHALL FOLLOW SPECIFICATION 079200.

THE JOINT MATERIAL AND SEALER SHALL BE PLACE WHERE THE PROPOSED ISLAND MEETS THE PROPOSED DRIVE LANE AND AROUND THE PROPOSED CATCH BASIN APRON IN TOLL LANES.

LEGEND

1. 3/4" CHAMFER
2. PERMISSIBLE 10" RADIUS
3. PERMISSIBLE 1" RADIUS

NOTES:

1. ALL REINFORCING STEEL SHALL BE EPOXY COATED.
2. SEE SHEET C–109 FOR JOINTING LOCATIONS.
3. SEE SHEET C–108 FOR CURB BOXES.

DETAIL A

EXPANSION JOINT DETAIL
(BETWEEN ISLAND SECTIONS)

DESIGN AGENCY
PRIME AE
540 White Pond Drive, Ste. E
Akron, Ohio 44320
(330)-864-7755

NO.	REVISIONS	BY	DATE
4	Addendum No. 4	LHB	2-17-23

DESIGNED LHBJ | CHECKED SMM | DRAWN LHBJ | IN CHARGE SMM

TOLL ISLANDS DETAILS

TRUMBULL COUNTY

TP239

PROJECT 58-22-01
DATE: 12/20/2022

C112

17
101

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

C:\Users\michael.brookbank\AppData\Local\Microsoft\Windows\INetCache\Content.Outlook\QLKFEK0A\10-14_TP239_58-22-01_MAB-bind.dwg; 2/17/2023 2:11 PM; michael.brookbank