LONG. JOINTS @ ENDS OF ISLANDS

N.T.S.

KEYED CONSTRUCTION JOINT

N.T.S.

JOINT TYPES

C – TRANSVERSE CONTRACTION JOINT WITH DOWELS. SEE ODOT STD. DWG. BP–2.1

K – KEYED JOINT SEE DETAIL THIS SHEET

L – LONGITUDINAL JOINT WITH TIE BARS. SEE ODOT STD. DWG. BP–2.1

ES – PRESSURE RELIEF JOINT WITH SLEEPER SLAB. SEE DETAIL SHEET C114.

EX – 1" EXPANSION JOINT WITHOUT DOWELS

NOTES

1. CONTRACTOR SHALL PROVIDE KEYED CONSTRUCTION JOINT AT THE END OF EACH DAY'S POUR. A MAXIMUM OF THREE LANES MAY BE POURED BETWEEN KEY JOINTS.

2. ALL STATIONS SHOWN ON THIS DRAWING ARE RELATIVE TO THE LOCAL TANGENT AT TURNPIKE C. L. STA. 1175+15 UNLESS OTHERWISE INDICATED.

DESIGN AGENCY
PRIME AE
540 White Pond Drive, Ste. E
Akron, Ohio 44320
(330)-864-7755

NO.	REVISIONS	BY	DATE
4	Addendum No. 4	LHB	2–17–23

DESIGNED	CHECKED	DRAWN	IN CHARGE
LHBJ	SMM	LHBJ	SMM

PAVEMENT AND JOINTING PLAN

TRUMBULL COUNTY

TP239

PROJECT 58-22-01

DATE: 12/20/2022

C109

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

C:\Users\lbowes\Documents\My Documents\Prime Projects\zz-Archive\OTIC\19418_TP4 TP49 TP211 TP239_19458\TP239_58-22-01\Design\Sheets\7-9_TP239_58-22-01_MAB-bind.dwg; 2/17/2023 11:57 AM; lew bowes