	ESTIMATED QUANTITY			ITEM DESCRIPTION
	ITEM	TOTAL	UNIT	
	IB. ART.6	1	LUMP	PREMIUM FOR CONTRACT PERFORMANCE BOND AND PAYMENT BOND
	202	51,100.00	FOOT	GUARDRAIL REMOVED
	202	1,000.00	FOOT	GUARDRAIL REMOVED FOR STORAGE
	202	10,930.00	FOOT	CURB REMOVED
*	204	200.00	CU.YD.	EXCAVATION OF SUBGRADE
*	204	100.00	CU.YD.	EMBANKMENT
*	204	300.00	SQ.YD.	SUBGRADE COMPACTION
	254	252,000.00	SQ.YD.	PAVEMENT PLANING, ASPHALT CONCRETE (T=1.5")
1	***254***	385,320.00	SQ.YD.	PAVEMENT PLANING, ASPHALT CONCRETE (T=3")
*	254	500.00	SQ.YD.	PAVEMENT PLANING, PORTLAND CEMENT CONCRETE, AS PER PLAN
*	SP 304	100.00	CU.YD.	AGGREGATE BASE
	SP 404	12.00	CU.YD.	ASPHALT CONCRETE SURFACE COURSE, USING CRUSHED STONE, PG 64-22
	SP 404	26,553.00	CU.YD.	ASPHALT CONCRETE SURFACE COURSE, USING CRUSHED SLAG, PG 76-22(FR)
	SP 402	16,100.00	CU.YD.	ASPHALT CONCRETE INTERMEDIATE COURSE, USING CRUSHED STONE, PG 76-22(FR)
**	SP 404A	***142,400.00*** 1	FOOT	JOINT SEALER
**	407	101,800.00	GALLON	NON-TRACKING TACK COAT
**	SP 451	3,670.80	SQ.YD.	FULL DEPTH PAVEMENT REPAIRS (ASPHALT)
*	SP 605	750.00	FOOT	AGGREGATE DRAINS, TYPE II
	606	46,037.50	FOOT	GUARDRAIL, TYPE MGS, USING LONG STEEL POSTS
	606	69.00	EACH	ANCHOR ASSEMBLY, MGS TYPE T, USING LONG STEEL POSTS
	606	39.00	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1, USING LONG STEEL POSTS
	606	21.00	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 2, USING LONG STEEL POSTS
	SP 606A	84.00	EACH	ANCHOR ASSEMBLY, MGS TYPE E
	609	10,930.00	FOOT	ASPHALT CONCRETE CURB, TYPE I, PG 64-22
	611	59.00	EACH	CATCH BASIN, ADJUSTED TO GRADE
	SP 611	5.00	EACH	CATCH BASIN, GRATE AND CASTING, AS PER PLAN
	SP 614	1	LUMP	MAINTAINING TRAFFIC, AS PER PLAN
	SP 614ZP	4,320.00	HOURS	ZONE PERSON
1	614	***400.00***	CU.YD.	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC, AS PER PLAN
	614	25.40	MILE	WORK ZONE LANE LINE, CLASS 1, 740.02 TYPE 1
	617	71,529.00	SQ.YD.	SHOULDER PREPARATION
	617	5,960.00	CU.YD.	COMPACTED AGGREGATE
	617	50	M. GAL.	WATER
	619	1	LUMP	FIELD OFFICE, AS PER PLAN
	621	1,700.00	EACH	RAISED PAVEMENT MARKERS REMOVED
	SP 621	1,700.00	EACH	RAISED PAVEMENT MARKERS
	SP 623	1	LUMP	CONSTRUCTION LAYOUT SURVEY
	624	1	LUMP	MOBILIZATION
	SP 626	400	EACH	BARRIER REFLECTOR, TYPE A (WHITE)
	SP 626	400	EACH	BARRIER REFLECTOR, TYPE A (YELLOW)
	SP 627	1,419.00	CU.YD.	STONE SHOULDER PROTECTION
**	642	27.40	MILE	6" WHITE LANE LINE, TYPE 1
**	642	27.40	MILE	6" WHITE EDGE LINE, TYPE 1
**	642	27.40	MILE	6" YELLOW EDGE LINE, TYPE 1
**	642	5,000.00	FOOT	12" WHITE CHANNELIZING LINE, TYPE 1
**	642	4,000.00	FOOT	DOTTED LINE, 6", WHITE, TYPE 1
	SPECIAL	13,333.00	SQ.YD.	EXISTING AGGREGATE DRAIN OUTLET CLEAN OUT
	SPECIAL	***50.32*** 1	MILE	SNAP FILL
	SPECIAL	50.32	MILE	SONIC NAP ALERT PATTERN (SNAP)
	SPECIAL	20.00	EACH	AIR SPEED ZONE MARKINGS, AS PER PLAN
*	SPECIAL	17,033.00	SQ.YD.	REGRADING UNDER GUARDRAIL
1	***614***	***75.50***	***MILE***	***WORK ZONE EDGE LINE, CLASS 1, 740.02 TYPE 1***
1 **	***897***	***3,670.80***	***SQ.YD.***	***PAVEMENT PLANING, ASPHALT CONCRETE***

2

* CONTINGENCY QUANTITY TO BE USED AS DIRECTED BY CHIEF ENGINEER (SEE GENERAL NOTES).

** PORTION OF THIS ITEM IS CONTINGENCY QUANTITY (SEE PLANS AND GENERAL NOTES).

59-23-01-010-012.dwg: 3/24/23 - 12:21pm

DESIGN AGENCY

NO.	REVISIONS	BY	DATE
1	ADDENDUM NO. 1	JJS	3/13/23
2	ADDENDUM NO. 2	JJS	3/27/23
-	-	-	-

DESIGNED JJS | CHECKED DAR | DRAWN JJS | IN CHARGE CAM

ESTIMATED QUANTITIES

PROJECT 59-23-01

10/12

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION