

**OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION**

ADDENDUM NO. 1

**PROJECT NO. 41-16-02
ASPHALT CONCRETE PAVEMENT SEALING
INDIAN MEADOW, TIFFIN RIVER, BLUE HERON, WYANDOT, ERIE ISLANDS, AND
COMMODORE PERRY SERVICE PLAZAS, MILEPOSTS 20.8, 76.9, AND
100.00, WILLIAMS AND SANDUSKY COUNTIES, OHIO**

OPENING DATE: 2:00 P.M. (EASTERN TIME), JUNE 10, 2016

ATTENTION OF BIDDERS IS DIRECTED TO:

ANSWERS TO QUESTIONS RECEIVED THROUGH 10:00AM ON JUNE 3, 2016

Issued by the Ohio Turnpike and Infrastructure Commission on June 3, 2016. Issuance authorized by Anthony D. Yacobucci, Chief Engineer, and Mark R. Musson, Director of Contract Administration.

 6/3/16

Anthony D. Yacobucci Date

 6/3/16

Mark R. Musson Date

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION
ADDENDUM NO. 1
PROJECT NO. 41-16-02

QUESTIONS AND ANSWERS THROUGH 10:00 AM JUNE 3, 2016

Q#1 Is there a phasing plan for each travel plaza?

A#1 No, however the Contractor(s) shall provide a phasing plan for approval per the Maintenance of Traffic & Site Access note of the General Notes on Plan Sheet 2 of 8. The Maintenance of Traffic & Site Access note gives specific requirements and restrictions for the phasing plan.

Q#2 How much area can we occupy at one time per location?

A#2 Per Maintenance of Traffic & Site Access note of the General Notes on Sheet 2 of 8, "The Phasing Plan shall include providing access to the site from/to the mainline Turnpike roadway, local road network, building doors, fuel islands parking areas, etc. throughout the duration of the Project. The Phasing Plan shall also allow for the use of a minimum of fifty (50) percent each of truck parking, passenger car parking, employee parking, bus parking and travel trailer parking as defined in the Plans. The phasing plan shall also allow for the use of a minimum of fifty (50) percent each of passenger car and truck fueling islands. Additionally, at least one (1) drive from/to the local roads shall be accessible at all times. Contractor shall maintain access to the plaza loading docks and shall coordinate operations with Plaza Manager to insure access is maintained."

Q#3 Are we able to work on multiple locations at the same time?

A#3 The Contractor(s) will be permitted to work at both Group I and Group II locations simultaneously; however, access to Group III is not anticipated until after the required completion date for Groups I & II. Please see the 'Additional Terms' on page 4 for more details and requirements of the different sites.

Q#4 What are the crack fill requirements before the seal coat material is applied?

A#4 The Contractor(s) are not required to perform crack filling. Per the Item Special – Asphalt Concrete Pavement Sealing note on Plan Sheet 2 of 8, "Pavement surface repairs, crack filling and stain treatment will be made by the Commission prior to the sealing operations."

Bidders Acknowledgment of Addendum No. 1
to Contract No. 41-16-02:

(Firm Name)

(Signature)

(Printed Name)

Date: _____