

OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION

ADDENDUM NO. 1

PROJECT NO. 53-16-02
REPAIRS AND RESURFACING
ERIE ISLANDS SERVICE PLAZA
MILEPOST 100.00
SANDUSKY COUNTY, OHIO


OPENING DATE: 2:00 P.M. (EASTERN TIME), APRIL 21, 2016


ALL BIDS MUST BE ELECTRONICALLY SUBMITTED THROUGH BID EXPRESS

ATTENTION OF BIDDERS IS DIRECTED TO:

QUESTIONS AND ANSWERS THROUGH 1:00 PM ON APRIL 18, 2016

Issued by the Ohio Turnpike and Infrastructure Commission on April 18, 2016. Issuance authorized by Anthony D. Yacobucci, Chief Engineer, and Mark R. Musson, Director of Contract Administration.


Anthony D. Yacobucci 4-18-16
Date


Mark R. Musson 4/18/16
Date

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION
ADDENDUM NO. 1
PROJECT NO. 53-16-02

QUESTIONS AND ANSWERS THROUGH 1:00 PM ON APRIL 18, 2016

Q#1 Is the MTD required to complete the parking lot pavement repairs?

A#1 Using a Material Transfer Device is not required for this Project.

Q#2 Will the Class I Inertial Profilometer will be required to test the smoothness of the patches?

A#2 Using a Class I Inertial Profilometer is not required for this Project.

Q#3 Regarding the note Item SP 623 – Construction Layout Stakes, APP. The note shall include providing all needed survey during resurfacing of the truck parking area to ensure the pavement has positive drainage in accordance with reference and information sheet 6. There are some areas (not designated for repairs) that are lightly rutted that have water holes. Is the contractor responsible for making sure there is positive drainage in the areas that don't get repaired? We are unsure how to maintain positive drainage flow for the entire truck area by fixing random areas and still have areas left that have rutting problems and will still trap water. Should a Pavement Planing (micromilling / diamond grinding) item be setup to address these potential issues?

A#3 The Contractor is not responsible for maintaining drainage for areas that Contractor is not repairing. The Contractor will be responsible for maintaining positive drainage for the areas where repairs are to be performed.

Addendum No. 1 to Contract 53-16-02:

(Firm Name)

(Signature)

(Printed Name)

Date: _____