



**OHIO TURNPIKE AND  
INFRASTRUCTURE COMMISSION**

**ADDENDUM NO. 1**

**PROJECT NO. 99-19-01**

**BRIDGE REPAIRS**

**THE OHIO TURNPIKE OVER U.S. RT. 6, M.P. 95.4  
SANDUSKY COUNTY, OHIO**


**OPENING DATE:**


**2:00 P.M. (EASTERN TIME), MAY 24, 2018**

**ATTENTION OF BIDDERS IS DIRECTED TO:**

**ANSWERS TO QUESTIONS RECEIVED THROUGH 5:00 PM ON MAY 13, 2019**

Issued by the Ohio Turnpike and Infrastructure Commission on May 14, 2019 by Anthony D. Yacobucci, Chief Engineer, and Mark R. Musson, Director of Contracts Administration.

  
Anthony D. Yacobucci      Date 5-14-19

 5/14/18  
Mark R. Musson      Date

**ANSWERS TO QUESTIONS RECEIVED THROUGH 5:00 PM ON MAY 13, 2019:**

**Q#1 Drawings do not indicate removal and re-installation of existing moment plate on Beam line F that is to be repaired by Heat Straightening. We believe this needs removed to perform heat straightening of beam. Please clarify.**

*A#1 The bottom flange splice plates may be removed as this splice is located at a point of dead load contraflexure. The web splice plates may not be removed because there is still significant shear at this location. Also, all live loading from traffic above must be kept off of the beam while the plates are removed. This requires a right shoulder closure which will be installed, maintained, and removed by the Ohio Turnpike and Infrastructure Commission.*

**Receipt of Addendum No. 1  
Project No. 99-19-01 is hereby acknowledged:**

(Firm Name) \_\_\_\_\_

(Signature) \_\_\_\_\_

(Printed Name) \_\_\_\_\_

(Date) \_\_\_\_\_

**BIDDERS MUST RETURN THE ABOVE ACKNOWLEDGEMENT  
OF RECEIPT OF ADDENDUM NO. 1 WITH THEIR BID.**