



**OHIO TURNPIKE AND  
INFRASTRUCTURE COMMISSION**

**ADDENDUM NO. 3**

**PROJECT NO. 43-18-05 (PART A)**  
**BRIDGE REPAIR AND REHABILITATION**  
**OHIO TURNPIKE RAMP OVER OHIO TURNPIKE (EXIT 218), M.P. 218.7**  
**MAHONING COUNTY, OHIO**

**PROJECT NO. 43-18-05 (PART B)**  
**BRIDGE REPLACEMENT**  
**OHIO TURNPIKE OVER MILL CREEK BIKEWAY, M.P. 223.0**  
**MAHONING COUNTY, OHIO**

**OPENING DATE:**  
***PREVIOUSLY EXTENDED TO 2:00 P.M. (EASTERN TIME), JUNE 1, 2018***

**ATTENTION OF BIDDERS IS DIRECTED TO:**  
**QUESTIONS RECEIVED THROUGH 1:00 PM ON MAY 24, 2018**  
**-AND-**  
**REVISIONS TO 43-18-05-PART B PLAN SHEET NOS. 13 AND 43 OF 57**  
**-AND-**  
**REVISIONS TO THE BID SCHEDULE OF ITEMS REF NOS. 22 AND 98**

Issued by the Ohio Turnpike and Infrastructure Commission on May 24, 2018 by Christopher A. Matta, Deputy Chief Engineer, and Mark R. Musson, Director of Contracts Administration.

  
Christopher A. Matta  
5/24/18  
Date

  
Mark R. Musson  
5/24/18  
Date

**ANSWERS TO QUESTIONS RECEIVED THROUGH 1:00 PM ON MAY 24, 2018:**

- Q#32 Addendum #1 answered Question #7 indicating that an average depth of 3 feet for the length of the culvert was used to quantify the excavation quantities; however, it is believed that some of this excavation is quantified in bid item #32 – Excavation. Cross Sections have been run through the bike path and the culvert quantifying the Cubic Yards of Excavation to the bottom of concrete for the bike path structure. Please clarify whether the Excavation will be paid under Bid Item #32 – Excavation or Bid Item #98 – Unclassified Excavation. Also, please adjust quantities as required.**
- A#32 The Bid Item #98 – unclassified excavation quantity has been revised to 342 CU. YD. to account for the excavation paid for by Bid Item #32 – Excavation. General Summary Plan Sheet 13 of 57, Structure Estimated Quantities Plan Sheet 43 of 57 and the Bid Schedule of Items have been revised through this Addendum 3.*
- Q#33 Addendum #1 answered Question #19 regarding Work Zone Pavement Markings and the last sentence of the answer states that “Part B is done separately, as indicated”. However, Part B does not have any bid items set up for Work Zone Pavement Markings and no notes indicating where the Work Zone Pavement Markings is to be paid. Please clarify.**
- A#33 Please see the “MAINTAINING TRAFFIC” note on Plan Sheet 6 of 57, Section VI. PAYMENT stating that “Payment for Maintenance of Traffic Items, unless specified separately, shall be paid for under the lump sum bid for Item 614 – Maintaining Traffic, which shall include all labor, equipment, materials, and incidentals required to complete the work as detailed in the plan”.*
- Q#34 Bid Item #22 – Micro-Silica Modified Concrete Overlay (Variable Thickness), Material Only is set up on the bid sheet to be paid by the Square Yard; however, Supplemental Specification 848 states that this item will be paid by the Cubic Yard. Please change the bid sheet to pay for this item by the Cubic Yard.**
- A#34 The correct unit for “Item #22 – Micro-Silica Modified Concrete Overlay (Variable Thickness), Material Only” is CU. YD. The Bid Schedule of Items has been revised through this Addendum 3.*
- Q#35 The existing/as-built construction drawings for the Turnpike Bridges over the Mill Creek Bikeway M.P. 223.0 still have not been posted online. Please post these drawings.**
- A#35 The existing/as-built construction drawings for the Turnpike Bridges over the Mill Creek Bikeway M.P. 223.0 are provided with this Addendum 3 in accordance with IB 2.1.4.*
- Q#36 In Addendum #1, answer to Question #9 states to access the project along the northeastern side of the Ohio Turnpike Right-of-Way and that the contractor must take every precaution and care to prevent any interference or damage to the CenturyLink’s fiber optic cable. Does**

**the Ohio Turnpike or Century Link have any information on the depth of the fiber optic cable between Kirk Rd and the Mill Creek Bikepath? Are there any as-built drawings on this cable that could be posted online?**

*A#36 The "As-Built" drawing for the CenturyLink fiber optic cable is provided "For Information Only" through this Addendum 3 in accordance with IB 2.1.4. Bidders are directed to Special Provision SP117 for additional details and provisions regarding CenturyLink's fiber optic cable.*

**Q#37 Would the Turnpike allow Project laydown and field office trailer at Salt Dome MP 219.0 EB?**

*A#37 The existing paved area near the salt dome at Eastbound MP 219 may be used for field office trailer location. The existing laydown area at the Westbound MP 219 area may be used for equipment and material storage during the project. The Contractor must restore the property to its condition immediately preceding its use, as approved by the Chief Engineer.*

**Q#38 Is precast coping allowed on top of the MSE wall?**

*A#38 As provided in ODOT Supplemental Specification 840.06.K, precast coping is not permitted on the MSE wall.*

**Receipt of Addendum No. 3**

**Project No. 43-18-05 (PART A & B) is hereby acknowledged:**

(Firm Name) \_\_\_\_\_

(Signature) \_\_\_\_\_

(Printed Name) \_\_\_\_\_

(Date) \_\_\_\_\_

**BIDDERS MUST RETURN THE ABOVE ACKNOWLEDGEMENT  
OF RECEIPT OF ADDENDUM NO. 3 WITH THEIR BID.**

GENERAL SUMMARY

Table with columns: ITEM NO., QUANTITY, UNIT, ITEM DESCRIPTION, REFERENCE NO. Includes sections: ROADWAY, EROSION CONTROL, DRAINAGE, PAVEMENT, TRAFFIC CONTROL.

GENERAL SUMMARY

Table with columns: ITEM NO., QUANTITY, UNIT, ITEM DESCRIPTION, REFERENCE NO. Includes sections: MAINTENANCE OF TRAFFIC, LIGHTING, GENERAL, STRUCTURES.

04\_OTMP223\_EQ1.dwg: 5/23/18 - 3:11pm

ESTIMATED QUANTITIES

ITEM NO.	QUANTITY	UNIT	ITEM DESCRIPTION	MP 223.0						
				CULVERT	MSE WINGWALL #1	MSE WINGWALL #2	MSE WINGWALL #3	MSE WINGWALL #4	REFERENCE SHEET	
SP 202	LUMP	LUMP SUM	PORTIONS OF STRUCTURE REMOVED	LUMP						
SP 202	343	SQ. YD.	APPROACH SLAB REMOVED	343						
503	342	CU. YD.	UNCLASSIFIED EXCAVATION, AS PER PLAN	342						8
SP 509	205,811	POUND	EPOXY COATED REINFORCING STEEL	205,811						
511	1,263	CU. YD.	CLASS QC1 CONCRETE	1,263						
511	1	EACH	CONCRETE, MISC.: MOCKUP PANEL	1						
511	864	SQ. FT.	CONCRETE, MISC.: FORMLINER	864						
512	1,005	SQ. YD.	SEALING OF CONCRETE SURFACES, AS PER PLAN (PERMANENT GRAFFITI PROTECTION)	173	263	112	295	162		8
512	2,061	SQ. YD.	TYPE 2 WATERPROOFING	2,061						
512	1,005	SQ. YD.	SEALING, MISC.: STAINING OF CONCRETE SURFACES	173	263	112	295	162		
516	70	SQ. FT.	1" PREFORMED EXPANSION JOINT FILLER	70						
518	1,027	CU. YD.	POROUS BACKFILL WITH FILTER FABRIC	1,027						
518	584	FOOT	6" PERFORATED CORRUGATED PLASTIC PIPE	584						
518	8	FOOT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	8						
SP 527	LUMP	LUMP SUM	FALSEWORK, TEMPORARY BRACING AND PROTECTIVE STRUCTURES	LUMP						
SP 536	1,005	SQ. YD.	CONCRETE WEATHERPROOFING	173	263	112	295	162		
611	216	FOOT	CONDUIT, TYPE A, PRECAST REINFORCED ARCH SECTIONS, AS PER PLAN (20'-SPAN X 10' RISE)	216						3 & 8
840	6,517	SQ. FT.	MECHANICALLY STABILIZED EARTH WALL		2,089	852	2,348	1,228		
840	2,189	CU. YD.	WALL EXCAVATION		850	219	933	187		
840	690	SQ. YD.	FOUNDATION PREPARATION		215	96	235	144		
840	4,371	CU. YD.	SELECT GRANULAR BACKFILL		1,407	522	1,669	773		
840	704	FOOT	6" DRAINAGE PIPE, PERFORATED CORRUGATED PLASTIC PIPE		240	90	241	133		
840	8	FOOT	6" DRAINAGE PIPE, NON-PERFORATED CORRUGATED PLASTIC PIPE		2	2	2	2		
840	318	FOOT	CONCRETE COPING		104	44	104	66		
840	4	DAYS	ON-SITE ASSISTANCE		1	1	1	1		
840	5,830	SQ. FT.	AESTHETIC SURFACE TREATMENT		1,843	764	2,127	1,096		
840	LUMP	LUMP SUM	SGB INSPECTION AND COMPACTION TESTING	LUMP	LUMP	LUMP	LUMP	LUMP		

DESIGN AGENCY  
**Bennett Fleming**  
OHIO TURNPIKE

BY DATE  
VDI 5/15/18  
VDI 5/23/18

REVISIONS  
ADDENDUM #1  
ADDENDUM #3

CHECKED  
NO. 1 2  
GTK IN CHARGE  
MTO

DESIGNED  
CJP DRAWN  
CJP

ESTIMATED STRUCTURE QUANTITIES  
OHIO TURNPIKE OVER MILL CREEK BIKEWAY  
MAHONING COUNTY  
M.P. 223.0

PROJECT 43-18-05B  
DATE: 4/27/18

4 / 18

43  
57

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

OHIO TURNPIKE