

OHIO TURNPIKE COMMISSION

ADDENDUM NO. 2

**BID INVITATION NO. 4189
INTERIOR AND EXTERIOR SERVICE PLAZA FURNITURE**

**OPENING DATE *EXTENDED* BY THIS ADDENDUM NO. 2:
2:00 P.M. (E.D.T.), ~~SEPTEMBER 25~~ *October 2*, 2012**

ATTENTION OF BIDDERS IS DIRECTED TO:

ANSWERS TO QUESTIONS RECEIVED THROUGH 5:00 P.M., SEPTEMBER 25, 2012

- AND -

MODIFICATIONS TO THE CONTRACT DOCUMENTS


COVER PAGE AND NOTICE TO BIDDERS

-and-

SPECIFICATIONS

Page 7a


Issued by the Ohio Turnpike Commission September 26, 2012. Authorized by Robin Carlin, Deputy Executive Director, and Mark Musson, Staff Attorney.



Robin Carlin



Date



Mark Musson



Date

ANSWERS TO QUESTIONS RECEIVED THROUGH 5:00 P.M., SEPTEMBER 25, 2012:

Q#1 I would like to propose an equal for the Ohio Turnpike Commission Project Bid Invitation No. 4189, for the Mahoning Valley Service Plaza and the Glacier Hills Service Plaza. The equals will be for Group I, Outdoor Picnic Tables, Items 1 and 2. I would like to propose, as equal, Extra Heavy-Duty Table (230) from Ultra-Site. I have attached cut sheets for both the 3 seat and 4 seat tables, along with warranty info and color and coat options. This Proposed Equal will require no changes in the contract documents.

A#1 *The Extra Heavy Duty Table (230) from Ultra Site is accepted as an approved equal because it meets the Specifications for Group I, Items 1 and 2, Outdoor Tables. The Specifications are modified via this Addendum No. 2 to reflect this approval.*

Q#2 In Group II we are proposing the use of Versteel Performance tables for both Items 1 and 2, in lieu of the specified Falcon Tables. We propose and certify that these tables are design equals and will perform in the same manner as the specified tables. The only difference is the specified tables are scheduled to receive a "MDI based, flexible elastomer urethane" bull nose edge. The Proposed Versteel tables will have their standard Wood Bullnose edge.

A#2. *The Versteel Performance Table is rejected as an approved equal because it fails to meet the Group II Specifications for the following reasons:*

- i. *The wood bullnose material is subject to finish damage and chipping in lieu of the specified MDI flexible elastomer urethane bullnose.*
- ii. *There was not enough information provided to determine compliance with the table top base material, column material and size, and base material and size.*

Q#3 In Group III we are proposing the use of Sit-On-It On Call 90 SC chairs and Fixtures Albi Chair. We will certify both chairs meet the requirements of the specifications and will perform the same. We ask that you review these substitution requests as they offer significant savings from the specified products. All three substitutions should not have any adverse affect on schedule or the project as a whole.

A#3. *The On-Call No. 90C Sit-On-It is rejected as an approved equal because it fails to meet the Specifications for Group III for the following reason:*

- i. *The chair frame is constructed out of 7/16-inch wire in lieu of the specified 12-gauge steel tubing.*

The Fixtures Albi Chair is rejected as an approved equal because it fails to meet the Group III Specifications for the following reasons:

- i. The chair frame is constructed out of 16-gauge steel tubing in lieu of the specified 12-gauge steel tubing.***
- ii. The seat and back are constructed out of thermoplastic in lieu of the specified polypropylene shell.***

Q#4 I would like to propose an equal for the Ohio Turnpike Commission Project Bid invitation No. 4189, for the Mahoning Valley Service Plaza and the Glacier Hills Service Plaza. The equals will be for Group III, Armless Stacking Chair. I would like to propose, as equal, H100 Series Wire Stack Chair from Falcon Products. I have attached a cut sheet for the chairs. This Proposed Equal will require no changes in the contract documents.

A#4 ***The Falcon H100 Series is rejected as an approved equal because the Bidder failed to provide sufficient information to enable the Commission to completely evaluate the Proposed Equal.***

Q#5 Please review the attached for a substitution request for Invitation 4189 Group III, Item 1 as a proposal to substitute Virco IQ Series to be an approved equal.

A#5 ***The Virco IQ Series is rejected as an approved equal because it fails to meet the Group III Specifications for the following reason:***

- i. The chair frame is constructed out of 13-gauge steel tubing in lieu of the specified 12-gauge steel tubing.***

Q#6 ERG who is specified in Groups III & IV is requesting your consideration of their request for substitution approval for the furniture specified in Group I Outdoor Furniture and Group II Food Court Tables. ERG would like your consideration of their Florin Cluster Roundabout in Group I Outdoor furniture. ERG would like your consideration of their Napoli Table in Group II Food Court Tables.

A#6 ***These requests for approval of proposed equals will be addressed in an Addendum No. 3.***

Q#7 Please let me know if you can accept the equal: Proposed equal for Group VI see below and attached. Understanding this item varies from look and design but still want to know if this is an option. For 'Group VI' we have the attached 55 gallon receptacle, liner and below lid: Below are the color options for thermoplastic (receptacle):

A#7 This request for approval of proposed equals will be addressed in an Addendum No. 3.

Q#8 Please let me know if you can accept the equal: Attached is the closest match for 'Group I' of the bid. As you can see from the specs on page 6 the table top and frame is slightly larger and higher than what the bid asks for. This table can come with all 4 seats along with the 3-seat ADA version and both can be surface mounted. The planking will come in a thermoplastic coating which is higher quality and the frame will come powder coated. Below are the color options for thermoplastic. Powder coat colors are below.

A#8 This request for approval of a proposed equal will be addressed in an Addendum No. 3.

Q#9 Please let me know if you can accept the equal: Group V' We have the attached receptacle, liner and lid. Below are the color options for thermoplastic (receptacle):

A#9 This request for approval of proposed equals will be addressed in an Addendum No. 3.

Q#10 Please let me know if you can accept the option: Proposed equal for Group VII see below and attached. Understanding design is different but would like to know if this is an option. At this time we do not have a cigarette receptacle that has a covered top which is what is being specified but is this a option? Below are the color options for thermoplastic (receptacle):

A#10 This request for approval of proposed equals will be addressed in an Addendum No. 3.

THE FOLLOWING MODIFICATIONS ARE MADE TO THE CONTRACT DOCUMENTS FOR INVITATION NO. 4189:

Modifications are shown with ***bold italicized*** text and deletions are shown with ~~strikethrough~~ text.

The Cover Page and Page 1a of the NOTICE TO BIDDERS are hereby modified to extend the Bid Opening Date from ~~September 25 28, 2012~~ to 2:00 P.M. (E.D.T.) on ~~September 25-28~~ ***October 2, 2012***.

Page 7a – SPECIFICATIONS ENTITLED “Group I Outdoor Picnic Tables”: The following modifications are made commencing with the sixth paragraph in the Section entitled “Group I Outdoor Picnic Tables, Item 1 – Outdoor Table with Three (3) Seats and Item 2 – Outdoor Table with Four (4) Seats”:

As a level of standard and design, furniture shall be Steelhead Carousel Series as manufactured by Landscape Forms, Inc , Kalamazoo, Michigan *or the Extra Heavy-Duty Table (230) as manufactured by Ultra-Site, a PlayCore Company, Rosebud, Illinois*. The color of the outdoor tables with integral seats shall be "stormcloud:" *for the tables from Landscape Forms and "brown" for the tables from Ultra-Site*. Approved equals in conformance with the above specifications shall be considered. (See page 2e, Section O for instructions on Proposed Equals).

The attached replaces the Cover Page, Page 1a of the Notice to Bidders, Page 7a in conjunction with the Contract Documents for Invitation No. 4189.

Receipt of Addendum No. 2 Invitation No. 4189, is hereby acknowledged:

(Firm Name) _____

(Signature) _____

(Printed Name) _____

(Date) _____

BIDDERS MUST RETURN THE ABOVE ACKNOWLEDGEMENT OF RECEIPT OF ADDENDUM NO. 2 WITH THEIR BID.

OHIO TURNPIKE COMMISSION

682 PROSPECT STREET

BEREA, OHIO 44017

PROCUREMENT DEPARTMENT

440-234-2081

BID INVITATION NO. 4189

FOR FURNISHING:

INTERIOR AND EXTERIOR SERVICE PLAZA FURNITURE

OPENING DATE:

2:00 P.M. (E.D.T), ~~SEPTEMBER 25~~ **OCTOBER 2**, 2012

SUBMITTED BY:

COMPANY NAME: _____

CONTACT NAME: _____

STREET ADDRESS: _____

CITY AND STATE: _____ ZIP: _____

TELEPHONE NUMBER: _____

FAX NUMBER: _____

EMAIL: _____

ATTACHMENTS:

- Bonding Requirements (1 Page)

Published and Copyrighted © 2012 by The Ohio Turnpike Commission

If you have received these Contract Documents from any entity other than the Ohio Turnpike Commission, you risk the receipt of inaccurate information and/or plans; and will not receive any addenda issued by the Commission. These documents are copyrighted by the Ohio Turnpike Commission. Any unauthorized electronic reproduction of these documents for the purpose of resale or bidding subscription services is expressly prohibited.

OHIO TURNPIKE COMMISSION

682 PROSPECT STREET
BEREA, OHIO 44017

NOTICE TO BIDDERS

INVITATION NO. 4189

Sealed Bids for furnishing to the Ohio Turnpike Commission, its requirements for Interior and Exterior Service Plaza Furniture, will be received in the office of the Procurement Manager at the principal office of the Commission, Ohio Turnpike Administration Building, 682 Prospect Street, Berea, Ohio 44017, until 2:00 P.M. (E.D.T.), September 25 28 October 2, 2012.

At said hour all Bids will be publicly opened and read.

The General Terms and Conditions, Specifications, Special Provisions, Bid, Affidavit, Contract and Performance Bond are on file and available to any interested person in the aforesaid Procurement Manager's office. These documents will be forwarded, upon request and without charge, to any prospective Bidder.

Each Bid must be on the form prescribed by the Commission and must comply with the terms and conditions set forth in the "Contract Documents."

Each Bid must be accompanied by a Combination Ten Percent (10%) Bid Guaranty Bond/Performance Bond Form covering Fifty Percent (50%) of the estimated Contract value, or a certified check, cashier's check or letter of credit on a solvent bank, payable to the order of the Ohio Turnpike Commission, in an amount not less than Ten Percent (10%) of the net total amount Bid, adjusted for a twenty (20) day term discount, if offered. These Bid Guaranty requirements are in conformance with the Ohio Revised Code Sections 153.54 and 9.312.

If a Combination Bid Guaranty/Performance Bond will be submitted by a Bidder, such bond must be on a form approved by the Commission. Approved bond forms are contained herein The certified check, cashier's check, letter of credit or Bid Guaranty Bond will be held by the Commission as a guaranty that, if any Bid is accepted, the Contract Documents will be executed and the performance of the Bid secured. Each such check, letter of credit or Bid Guaranty Bond, or the proceeds thereof, will be returned or retained as provided in the General Terms and Conditions.

SPECIFICATIONS

GROUP I **SERVICE PLAZA OUTDOOR FURNITURE**

It is the purpose of these Specifications to describe indoor and outdoor furnishings of the type for which Bids are solicited, pursuant to the Bid Invitation of which these Specifications form a part. The furnishings described herein, shall be standard production, of the type intended for use in a commercial food court type and service area environment, except where otherwise specifically indicated

Group I **Outdoor Picnic Tables**

Item 1 - Outdoor Table with Three (3) Seats

Item 2 - Outdoor Table with Four (4) Seats

The outdoor furniture shall be three (3) or four (4) seat models and shall be integrally designed as a single unit and shall be furnished with surface mount brackets to permit anchoring to existing concrete pavement. Anchoring of furniture shall be performed by the Ohio Turnpike Commission.

Tabletops shall be forty-two (42) inch diameter, one and one-half (1-½) inch outside diameter (O.D.) frame with 12-gauge steel perforated insert. Each tabletop shall have an umbrella hole and grommet hole cover.

Height of tabletop shall be twenty-eight and one-half (28-½) inches above floor. The table and seat supports shall be two (2) inch diameter steel tubing with a 0.120-inch wall thickness.

Seats shall be backed, perforated, and shall be permanently attached to the table frame, constructed of 14-gauge perforated metal panel with one-quarter (1/4) inch square holes on seven-sixteenths (7/16) inch straight centers in a seven-eighths (7/8) inch diameter, 0.120-inch wall thickness steel frame. Each table shall have three (3) or four (4) seats as detailed on the Form of Proposal. The three (3) seat configurations shall be designed for wheelchair accessibility.

The paint finish on all metal surfaces shall consist of a rust inhibiting and corrosion resistant epoxy prime coat and a separate thermosetting polyester powder coat finish. The powder coat shall consist of two coats of UV stabilized, impact resistant powder coat with a dry film thickness of approximately six (6) mils.

As a level of standard and design, furniture shall be *Steelhead Carousel Series* as manufactured by Landscape Forms, Inc., Kalamazoo, Michigan *or the Extra Heavy-Duty Table (230) as manufactured by Ultra-Site, a PlayCore Company, Rosebud, Illinois.* The color of the outdoor tables with integral seats shall be "stormcloud" *for the tables from Landscape Forms and "brown" for the tables from Ultra-Site.* Approved equals in conformance with the above specifications shall be considered. (See page 2e, Section O for instructions on Proposed Equals).