

OHIO TURNPIKE COMMISSION

ADDENDUM NO. 2

CONTRACT NO. 39-13-02
EASTBOUND RIGHT TWO (2) LANES AND SHOULDER RECONSTRUCTION
MILEPOST 164.82 TO MILEPOST 169.74
CUYAHOGA COUNTY, OHIO

OPENING DATE: ***EXTENDED TO*** 2:00 P.M. (E.S.T.), JANUARY 24 **28**, 2013


ATTENTION OF BIDDERS IS DIRECTED TO:


ANSWERS TO QUESTIONS RECEIVED THROUGH 10:00 A.M., JANUARY 18, 2013

MODIFICATIONS TO THE CONTRACT DOCUMENTS

Pages revised: Cover Page and OTC-NB-2

Issued by the Ohio Turnpike Commission January 18, 2013. Issuance authorized by Robin Carlin, Deputy Executive Director and Kathleen Weiss, General Counsel.


Robin Carlin
1/18/13
Date


Kathleen Weiss
1/18/13
Date

**OHIO TURNPIKE COMMISSION
ADDENDUM NO. 2
CONTRACT NO. 39-13-02**

ANSWERS TO QUESTIONS RECEIVED THROUGH 12:00 P.M., JANUARY 18, 2013

Q#6 Ref. #54 – Paved Gutter Misc. – What is required for this item, no details or APP notes to indicate the extent of work involved. Please provide information so the contractors can price accordingly.

A#6 A new General Note "Item 601 – Paved Gutter, Misc.: Gutter Broken in Place" will be added to clarify this Item on Plan Sheet 12 of 165 via Addendum No. 3 that states as follows: "ITEM 601 - PAVED GUTTER, MISC.: GUTTER BROKEN IN PLACE EXISTING GROUND. POSITIVE DRAINAGE SHALL BE MAINTAINED THROUGHOUT THE CHANNEL. THE CHANNEL SHALL BE 16' WIDE WITH 8' BOTTOM AND 4' WIDE SIDES AT 4:1 SLOPE OR MATCH THE CHANNEL IN CONJUNCTION WITH ROCK CHANNEL PROTECTION PROVIDED IN THE PLANS. AT THE EXCAVATED BOTTOM, THE CONTRACTOR SHALL PLACE THE BROKEN CONCRETE IN FROM THE CHANNEL, EXCAVATE BOTTOM OF THE CHANNEL 2 FEET AND PLACE FABRIC FILTER AS ROCK CHANNEL PROTECTION. THE CONTRACTOR SHALL REMOVE THE BROKEN CONCRETE THIS ITEM INCLUDES BREAKING UP THE PAVED GUTTER CONCRETE IN PLACE TO BE USED."

Q#11 Item SP514A Field Painting Misc.: Field Paint Bearings does not specify which bearings are to be painted. Are all bearings being painted? Are bearings on abutments and/or piers?

A#11 The bearings are located on both abutments and piers as indicated on the Bearing Rehabilitation and Repair Table on Plan Sheet 154 of 165. The Bearing Rehabilitation and Repair Table on Plan Sheet 154 of 165 details the extent of all bearing Work. The only bearings to be painted are those bearings indicated to be painted in SP 514(A) or rebuilt as per SP 516(K).

Q#12 On Structure Royalton Road MP 165.4 you call for 95 bearings. The Eastbound structure only has 72 bearings. Are there bearings to be painted on the Westbound part of the structure? Are bearings on other structures in the Westbound lanes?

A#12 Repair Work is to be performed on both the Eastbound and Westbound structures. Refer to the Bearing Rehabilitation and Repair Table on Plan Sheet 154 of 165 for locations of repair Work.

Q#13 If bearings are included in the westbound lane this would drastically increase the cost due to additional containment areas. Please clarify your intentions.

A#13 The Contract Documents call for the replacement or repair of all deficient bearings on both Eastbound and Westbound structures. See Bearing Rehabilitation and Repair Table on Plan Sheet 154 of 165.

Q#14 Plan notes and details on Pg. 102A indicate that the excavated material from the slope benching is to be re-used as the embankment in the same location. Note 3 indicates that inclusion of limestone sand will be required. What is the application rate for the limestone sand and how is the contractor compensated for this activity?

A#14 The Commission will answer this question in Addendum No. 3.

Q#15 Note (10) on the same page then indicates that embankment material that is supplied must meet the stated requirements and testing. Is new embankment required or not?

A#15 The Commission will answer this question in Addendum No. 3.

Q#16 Are removal of existing approach slabs (which will be replaced under bridge maintenance line items) included in the pavement removal bid item (ref. 13) or in the portions of structure removed bid items (ref. 104,127,150,173)?

A#16 The payment for the removal of the existing approach slabs is included in Item SP 202 - Portions of Structure Removed, and included on the Bid Form in Reference Nos. 104, 127, 150 and 173.

Q#17 Plan sheet 108 shows trench details for 603F pipes and SP605 underdrain. The SP605 specifications in the proposal designate different minimal trench widths. Please clarify which of these prevails for these referenced pipes and underdrains.

A#17 The minimum trench width specified in Special Provision SP 605 applies to this Work.

Q#18 For the 2012 project, the OTC offered two areas for disposal of materials (the IR 71 interchange yard and the EB Towpath site off the travel plaza). Will these sites be made available for this project for disposal of materials?

A#18 No, the Contractor shall remove all excess materials in accordance with SP 105.

**MODIFICATIONS VIA ADDENDUM NO. 2 TO THE CONTRACT DOCUMENTS FOR
CONTRACT NO. 39-13-02**

The following changes are made to the Contract Documents for Contract No. 39-13-02:

Modifications to the Cover Sheet and Notice to Bidders

Deletions are shown with ~~strikethrough~~ text.

Changes/Additions are shown with ***bold italicized*** text.

Cover Sheet and Notice to Bidders Page OTC-NB-2: The Bid Opening date has been extended from 2:00 P.M. (E.S.T) January 24, 2013 to 2:00 P.M. (E.S.T.) on January **28**, 2013.

ATTACHMENTS:

Cover Page and OTC -NB-2

(BIDDERS ARE ADVISED TO UTILIZE THE ATTACHED REPLACEMENT PAGES).

Receipt of Addendum No. 2 to Contract No. 39-13-02 is hereby acknowledged:

(Firm Name)

(Signature)

(Printed Name)

Date: _____

**Ohio Turnpike Commission
682 Prospect Street
Berea, Ohio 44017**

CONTRACT NO. 39-13-02

**EASTBOUND RIGHT TWO (2) LANES
AND SHOULDER RECONSTRUCTION
MILEPOST 164.82 TO MILEPOST 169.74
CUYAHOGA COUNTY, OHIO**

OPENING DATE: 2:00 P.M. (E.S.T.), JANUARY 24 28, 2013

Submitted By:

Company Name: _____

Contact Name: _____

Street Address: _____

City: _____

State: _____ Zip Code: _____

Telephone Number: _____

Fax Number: _____

Email: _____

Published and Copyrighted © 2013 by The Ohio Turnpike Commission

If you have received these Contract Documents from any entity other than the Ohio Turnpike Commission, you risk the receipt of inaccurate or incomplete information and/or Plans; and will not receive any addenda issued by the Commission. These documents are copyrighted by the Ohio Turnpike Commission. Any unauthorized electronic reproduction of these documents for the purpose of resale or bidding subscription services is expressly prohibited.

Bids will be accepted until **January 24 28, 2013, at 2:00 P.M (E.S.T.)**, when all Bids will be opened and read aloud. To avoid a potential extension of the Bid Opening date and/or a potential rejection of all Bids, it is imperative that Bidders submit all questions in a timely manner and no later than seven (7) days prior to Bid Opening.

Contract Documents are available by contacting the Commission's Procurement Department, 682 Prospect Street, Berea, Ohio 44017, Telephone (440) 234-2081.

The Contract Documents may be reviewed for bidding purposes without charge during business hours at the following locations:

Builders Exchange
9555 Rockside Rd, Ste. 300
Valley View, Ohio 44125
216-393-6300

Ohio Construction News
7261 Engle Rd, Suite 304
Cleveland, Ohio 44130
440-826-4700

A Contract will be awarded, if any award be made, to the Bidder determined to have submitted the lowest responsive and responsible Bid for the performance of the Work. The Commission reserves the right to reject any and all Bids and to waive minor irregularities or technical deficiencies.

OHIO TURNPIKE COMMISSION
Procurement Department

D.R. 1(3 & 10) 2013