

SPECIAL PROVISIONS

embankment for grading preparation of the entire toll plaza site, performing drainage installations, guard rail installation, constructing full depth asphalt pavement, installation of pavement markings and other traffic control devices on both the north and south side of the Ohio Turnpike.

Details of this Work and other incidental Work are shown on the Plans and/or described in the Specifications and these Special Provisions.

Pre-bid Questions shall be submitted in accordance with Articles 1.3.3 and 1.3.4 of Part 3 - Instructions to Bidders.

No verbal Questions will be considered.

SP 102

SPECIFICATIONS (12-2017)

All Work under this Project is to be constructed under the applicable sections of the Construction and Material Specifications ("CMS") of the State of Ohio Department of Transportation ("ODOT"), dated January 1, 2016, except Section 100 - General Provisions thereof, and Supplemental Specifications, unless another edition of the ODOT CMS is specified, and in accordance with the General Conditions of the Commission, these Special Provisions, the payment items listed on the Bid Form, and the terms and conditions of the Contract Documents. If there is reference to Section 100 of the ODOT CMS in other sections of the CMS, the appropriate provision of Section 100 shall apply and be operative, unless there is a specific statement to the contrary in the General Conditions, Special Provisions, and terms and conditions of the Contract Documents of the Commission. Whenever the word "Director" appears in the ODOT CMS, it shall be construed to mean the "Commission" or the "Chief Engineer" of the Commission, as set forth in the definitions of the Contract Documents.

SP 103

CONSTRUCTION PHASING AND TIME OF COMPLETION (06-2020)

The Work shall be performed and completed in its entirety in strict accordance with the Plans, Specifications, Special Provisions and other Contract Documents as follows:

2020 CONSTRUCTION SEASON

All Work associated with the removal and replacement of the Eastbound and Westbound left lane and median shoulder approach slabs with any associated asphalt paving, Eastbound and Westbound ORT Slab Construction for the left lane and median shoulder, installation of ORT Gantry Median Foundations and associated median wall construction, all proposed sign foundations within the median wall and associated median wall construction and construction of high speed median crossovers at mileposts 208.0 and 212.9, including all Project Work as described in the Contract Documents for Project No. 39-20-03 Part A. All work associated with both north and south toll plaza sites as described in the Contract Documents for Project No. 39-20-03 Part B Work Items shall include removing trees, clearing and grubbing, new fence installation around all new right of way, install all required SWPPP, **Construct embankment and** grade both sites **to provide positive drainage to the proposed ditches with a minimum depth of 2 foot below the new embankment to the subgrade elevations,** and ~~provide positive drainage by grading all~~ **Construct the proposed** ditches ~~and to drain the area~~ around the new toll plaza sites **including the detention basins.**