RAMP WITH GUARDRAIL
TYPICAL SECTION 1

RAMP WITHOUT GUARDRAIL
TYPICAL SECTION 1

RAMP WITH GUARDRAIL
TYPICAL SECTION 2

RAMP WITHOUT GUARDRAIL
TYPICAL SECTION 2

RAMP 1–4 AND 7–8 TYPICAL FOR PARAPET WORK
TYPICAL SECTION 5

RAMP 1–4 AND 7–8 TYPICAL FOR PARAPET WORK
TYPICAL SECTION 5

RAMP WITH TRAFFIC INSIDE
TYPICAL SECTION 3

RAMP WITH TRAFFIC INSIDE
TYPICAL SECTION 3

RAMP WITH GUARDRAIL
TYPICAL SECTION 4

RAMP WITHOUT GUARDRAIL
TYPICAL SECTION 4

ITEM 614 – WORK ZONE IMPACT ATTENUATOR

THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING A NON–GATING WORK ZONE IMPACT ATTENUATOR. THE FURNISHED WORK ZONE IMPACT ATTENUATOR SHAL BE SUPPLIED FROM THE ODOT OFFICE OF ROADWAY ENGINEERING'S APPROVED PRODUCTS LIST FOR WORK ZONE IMPACT ATTENUATORS.

INSTALLATION SHALL BE AT THE LOCATIONS SHOWN IN THE PLANS AND IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.

THE CONTRACTOR SHALL REPAIR OR REPLACE A DAMAGED UNIT WITHIN 24 HOURS OF A DAMAGING IMPACT.

THIS ITEM SHALL ALSO INCLUDE ALL LABOR, TOOLS, EQUIPMENT AND MATERIALS NECESSARY TO CONSTRUCT AND MAINTAIN A COMPLETE AND FUNCTIONAL IMPACT ATTENUATOR SYSTEM, INCLUDING ALL RELATED BACKUPS, TRANSITIONS, LEVELING PADS, HARDWARE AND GRADING, NOT SEPARATELY SPECIFIED, AS CALLED FOR BY THE MANUFACTURER. THIS ITEM SHALL ALSO INCLUDED THE SETUP, RELOCATION, AND REMOVAL OF THE WORK ZONE IMPACT ATTENTUATOR AS CALLED FOR IN THE PLANS.

PAYMENT FOR THIS ITEM SHALL BE CONSIDERED INCIDENTAL TO ITEM SP 614 – MAINTAINING TRAFFIC, AS PER PLAN.

DESIGN AGENCY

NO	REVISIONS	BY	DATE
1	ADDENDUM NO. 1	JJS	12/29/22

DESIGNED	CHECKED
JJS	RMS
DRAWN	IN CHARGE
JJS	CAM

MAINTENANCE OF TRAFFIC
TYPICALS

PROJECT 59-22-03

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

59-22-03-011-012.dwg: 12/29/22 - 10:55am