



**OHIO TURNPIKE AND  
INFRASTRUCTURE COMMISSION**

**ADDENDUM NO. 2**  
**ISSUED: NOVEMBER 1, 2024**

**PROJECT NO. 59-25-04**

**REPAIRS AND RESURFACING EASTBOUND AND WESTBOUND ROADWAYS M.P. 59.50 TO  
M.P. 73.95 LUCAS AND WOOD COUNTIES, OHIO**

**ISSUED OCTOBER 17, 2024**

**OPENING DATE: 2:00 P.M.(EASTERN TIME) NOVEMBER 7, 2024**

**ATTENTION OF BIDDERS IS DIRECTED TO:**

**ANSWERS TO QUESTIONS RECEIVED THROUGH 9:00 A.M. ON NOVEMBER 1, 2024**

Issued by the Ohio Turnpike and Infrastructure Commission through Aimee W. Lane, Esq., Director of Contracts Administration.

*Aimee W. Lane*

\_\_\_\_\_  
Aimee W. Lane, Esq.,  
Director of Contracts Administration

November 1, 2024  
Date

**ANSWERS TO QUESTIONS RECEIVED THROUGH 9:00 A.M. ON NOVEMBER 1, 2024:**

**Q#6** The MOT shown on Sheet 15 depicts special OTIC grabber cones in Phases 1, 2, and 6. Since these are such quick phases of the job, can the Contractor utilize drums in lieu of bringing out additional material? If not, will it be allowable to utilize standard ODOT cones for this work in lieu of the special OTIC cones?

*A6# The contractor may utilize drums in place of the suggested grabber cones provided traffic can be maintained and project work can be performed.*

**Q#7** Is SP404A required on longitudinal joints prior to paving intermediate and leveling courses? If so, has additional linear footage in the SP404A bid item been included for shooting cold joints prior to paving the intermediate and leveling course?

*A#7 SP 404A, Joint Sealer, is not required prior to paving the intermediate and leveling course.*

**END OF ADDENDUM NO. 2**