



**OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION**

ADDENDUM NO. 3
ISSUED: NOVEMBER 1, 2024

PROJECT NO. 59-25-04

**REPAIRS AND RESURFACING EASTBOUND AND WESTBOUND ROADWAYS M.P. 59.50 TO
M.P. 73.95 LUCAS AND WOOD COUNTIES, OHIO**

ISSUED OCTOBER 17, 2024

OPENING DATE: 2:00 P.M.(EASTERN TIME) NOVEMBER 7, 2024

ATTENTION OF BIDDERS IS DIRECTED TO:

ANSWERS TO QUESTIONS RECEIVED THROUGH 1:00 P.M. ON NOVEMBER 1, 2024

Issued by the Ohio Turnpike and Infrastructure Commission through Aimee W. Lane, Esq., Director of Contracts Administration.

Aimee W. Lane

Aimee W. Lane, Esq.,
Director of Contracts Administration

November 1, 2024
Date

ANSWERS TO QUESTIONS RECEIVED THROUGH 1:00 P.M. ON NOVEMBER 1, 2024:

Q#8 Is SP404A Joint Sealer intended to be placed on the cold joints after all paving is completed?

A8# SP 404A, Joint Sealer, is to be placed on the vertical face of the cold joint prior to placing the surface course material. It is not intended to be placed on the cold joint after the paving is complete.

END OF ADDENDUM NO. 3