

**OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION
SPECIAL PROVISIONS FOR
PROJECT 59-22-04**

SP 1 **GENERAL - INCLUDING MODIFICATIONS TO OHIO TURNPIKE
GENERAL CONDITIONS**

SP 101 **PLANS AND DESCRIPTION OF THE WORK**

The Work included in this Project, together with other pertinent information is shown and described in the Plans, which consist of a title sheet and other drawings, as tabulated on the index of sheets, covering details of the Work.

The title sheet for Project(s) No. 59-22-04 bears the general title as follows:

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION
THE JAMES W. SHOCKNESSY OHIO TURNPIKE

PROJECT 59-22-04
PART A: REPAIRS AND RESURFACING
EASTBOUND AND WESTBOUND ROADWAYS
MILEPOST 178.05 TO MILEPOST 185.65
PART B: REPAIRS AND RESURFACING
INTERCHANGE 187 RAMPS
MILEPOST 187.20
SUMMIT AND PORTAGE COUNTIES, OHIO

The title sheet bears the approval of the Chief Engineer.

The Work to be performed consists of the following:

Part A:

Removal by milling of three (3) inches of existing asphalt pavement in the center and right lanes of the mainline, removal by milling of two (2) inches of existing asphalt in the ~~left lane~~ and left and right shoulder, mill and fill of the Sonic Nap Alert Pattern ("SNAPs") in the left shoulder, resurfacing of the pavement and shoulders to the thickness specified in the Drawings, concrete approach slab removal and replacement, patching of concrete bridge decks and abutment slabs, concrete weatherproofing of bridges, full depth pavement repairs, installation of raised pavement markers and permanent pavement striping and/or other pavement markings, upgrading of guardrail, installation of SNAPs, and temporary traffic control, in both Eastbound and Westbound lanes.

Part B:

Removal by milling of three (3) inches of existing asphalt pavement on the interchange pavement and shoulders, resurfacing of the interchange pavement and shoulders to the thickness specified in the Drawings, full depth concrete pavement repairs of portions of interchange ramp pavement, installation of raised pavement markers and permanent pavement striping and/or other pavement markings, upgrading of guardrail, temporary traffic and all other items incidental to the completion of the Work.

Details of this Work and other incidental Work are shown on the Plans and/or described in the Specifications and these Special Provisions.

Pre-bid Questions should be submitted in accordance with Sections 1.3.3 and 1.3.4 of Article 1 of the Instruction to Bidders.

No verbal Questions will be considered.