



**OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION**

ADDENDUM NO. 1
ISSUED: JULY 24, 2026

PROJECT NO. 99-24-13

**BRIDGE REPAIR OHIO TURNPIKE OVER MAHONING AVE. M.P. 219.8 MAHONING
COUNTY, OHIO**

ISSUED JULY 9, 2026

OPENING DATE: 2:00 P.M.(EASTERN TIME) JULY 30, 2026

ATTENTION OF BIDDERS IS DIRECTED TO:

ANSWERS TO QUESTIONS RECEIVED THROUGH 12:00 P.M. ON JULY 24, 2026

MODIFICATIONS TO THE CONTRACT DOCUMENTS

Revised Plan Sheets: 1, 2 of 6

Issued by the Ohio Turnpike and Infrastructure Commission through Aimee W. Lane, Esq., Director of Contracts Administration.

Aimee W. Lane /kjg

Aimee W. Lane, Esq.,
Director of Contracts Administration

July 24, 2026
Date

ANSWERS TO QUESTIONS RECEIVED THROUGH 12:00 P.M. ON JULY 24, 2026:

Q#1 Will there be any permits required from city or county? If so, will there be a pay item for permit fees?

A#1 Contractor shall secure all necessary permits to complete the work as per SP 614. Permitting fees are intended as incidental to SP 614 and will not be itemized separately.

Q#2 What is the Federal paint code to be used for Item 514 field painting?

A#2 Topcoat color shall match color of existing paint (Green per Federal Standard 595B-14159).

Q#3 On sheet 5/6, Plan View, it states “Damage Stiffener (A) To Be Repaired, See Notes This Sheet”. Please provide the repair note.

A#3 Plan intent is for stiffener to be heat straightened. Additional notes are not required. No plan sheet revision provided.

Q#4 What is the Grade of steel required for Item 513 material?

A#4 The grade of steel for Item 513 is ASTM A709 Grade 50 ($F_y = 50$ ksi).

Note: Plan sheets 1 and 2 have been revised and included with Addendum No. 1.

END OF ADDENDUM NO. 1