



**OHIO TURNPIKE AND  
INFRASTRUCTURE COMMISSION**

**ADDENDUM NO. 2**  
**ISSUED: JULY 2, 2026**

**PROJECT NO. 43-26-12**

**BRIDGE DECK OVERLAY & REHABILITATION  
WEST 130<sup>TH</sup> ST. (C.R. 48) OVER OHIO TURNPIKE M.P. 163.8, OHIO TURNPIKE OVER  
INFIRMARY RD. (C.R. 164) M.P. 193.1, ELLSWORTH-BAILEY RD. OVER OHIO TURNPIKE  
M.P. 215.4, OHIO TURNPIKE OVER INDIAN RUN M.P. 228.6  
CUYAHOGA, PORTAGE, TRUMBULL, AND MAHONING COUNTIES, OHIO**

**ISSUED JUNE 18, 2026**

**OPENING DATE: 2:00 P.M.(EASTERN TIME) JULY 9, 2026**

**ATTENTION OF BIDDERS IS DIRECTED TO:**

**ANSWERS TO QUESTIONS RECEIVED THROUGH 2:00 P.M. ON JULY 2, 2026**

**MODIFICATIONS TO THE CONTRACT DOCUMENTS**

Revised Plan Sheet: 2

Issued by the Ohio Turnpike and Infrastructure Commission through Aimee W. Lane, Esq., Director of Contracts Administration.

*Aimee W. Lane*

\_\_\_\_\_  
Aimee W. Lane, Esq.,  
Director of Contracts Administration

July 2, 2026  
Date

**ANSWERS TO QUESTIONS RECEIVED THROUGH 2:00 P.M. ON JULY 2, 2026:**

**Q#4 Plan note page 2/22 Sequence Of Construction calls out short term stationary daytime zones are anticipated for installation of false work and full depth repair form work. according to the allowable lane closure chart for this project there is not any daytime two lane closures allowed. How is the contractor to work over the center lane of the turnpike?**

*A4 Lane closures are to be per the permitted lane closure charts. The plan note on sheet 2 has been revised for clarity and is included in this addendum.*

**Q#5 Will the contractor be required to install falsework/overhangs outside the fascia beams? The falsework details in the plans only show interior bay falsework.**

*A#5 Bidders shall review SP 527 which is included in this project. Contractors shall follow "Detail A" per SP 527 for the installation of falsework/overhangs outside of the fascia beams. Contractor shall submit a detailed falsework plan per SP 527 to the Commission for review and approval. No inspection walkway access will be needed as part of this work.*

**Q#6 Will the general contractor be required to install falsework on overhangs for mainline and overhead bridges receiving micro-silica modified concrete overlay?**

*A#6 See A#5.*

**Q#7 Is it anticipated that the on-going OTC project below MP 215.4 will be completed this calendar year?**

*A#7 The pavement replacement project below MP 215.4 has a substantial completion date of November 13, 2026.*

**END OF ADDENDUM NO. 2**