GENERAL SUMMARY			
ESTIMATED			
QUANTITY			ITEM DESCRIPTION
ITEM	TOTAL	UNIT	
IB. ART. 6	LUMP		PREMIUM FOR CONTRACT PERFORMANCE BOND AND PAYMENT BOND
201	LUMP		CLEARING AND GRUBBING, AS PER PLAN
202	465	SQ. YD.	PAVEMENT REMOVED
202	383	FOOT	CURB REMOVED
202	414	FOOT	GUARDRAIL REMOVED
202	2	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED
202	149	FOOT	PIPE REMOVED, 24" AND UNDER
202	2	EACH	CATCH BASIN REMOVED
202	51	FOOT	FENCE REMOVED
SP 202	LUMP		PORTIONS OF STRUCTURE REMOVED
203	2425	CU. YD.	EXCAVATION
203	3674	CU. YD.	EMBANKMENT, AS PER PLAN
203	3674	CU. YD.	BORROW, AS PER PLAN
204	1	HRS.	PROOF ROLLING
204	250	CU. YD.	EXCAVATION OF SUBGRADE
204	250	CU. YD.	EMBANKMENT, AS PER PLAN
302	80	CU. YD.	ASPHALT CONCRETE BASE, PG64-22, (449)
SP304	167	CU. YD.	AGGREGATE BASE
407	57	GALLON	NON-TRACKING TACK COAT
441	17	CU. YD.	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22
441	23	CU. YD.	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449)
507	1,044	FOOT	STEEL PILES, MISC.: W24X162, FURNISHED
SP 509	282	LB.	EPOXY COATED REINFORCING STEEL, GRADE 60
510	30	EACH	DOWEL HOLES WITH NONSHRINK , NONMETALLIC GROUT
SP 511B	2	CU. YD.	CLASS S CONCRETE, BARRIERS AND PAPAPETS, USING TYPE 1 CEMENT
SP 516B	2	FOOT	SEALING OF CONSTRUCTION JOINTS
524	1,056	FOOT	DRILLED SHAFTS, 36" DIAMETER, AS PER PLAN
524	1,012	FOOT	DRILLED SHAFTS, MISC.: PLUG PILE, 36" DIAMETER, UNREINFORCED
601	3	CU. YD.	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER, AS PER PLAN
601	2	SQ. YD.	TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT
605	383	FOOT	6" SHALLOW PIPE UNDERDRAINS WITH GEOTEXTILE FABRIC
605	50	FOOT	6" UNCLASSIFIED PIPE UNDERDRAINS
606	388	FOOT	GUARDRAIL, TYPE MGS WITH LONG STEEL POSTS
606	1	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1, USING LONG STEEL POSTS
606	1	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 2
607	51	FOOT	FENCE, TYPE 47
609	383	FOOT	ASPHALT CONCRETE CURB, TYPE 1, PG64-22
611	50	FOOT	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS
611	1	EACH	PRECAST REINFORCED CONCRETE OUTLET
SP 611	141	FOOT	12" CONDUIT, TYPE F, 707.33
SP 611	2	EACH	CATCH BASIN, NO. CB-1

GENERAL SUMMARY			
ESTIMATED			
QUANTITY			ITEM DESCRIPTION
ITEM	TOTAL	UNIT	
SP 614	LUMP		MAINTAINING TRAFFIC, AS PER PLAN
619	LUMP		FIELD OFFICE, AS PER PLAN
620	1	EACH	DELINEATOR, POST GROUND MOUNTED, AS PER PLAN
SP 623	LUMP		CONSTRUCTION LAYOUT STAKES AND SURVEYING
624	LUMP		MOBILIZATION
SP 626	5	EACH	BARRIER REFLECTOR, TYPE A (WHITE)
630	1	EACH	REMOVAL OF OVERHEAD MOUNTED SIGN AND REERECTION, AS PER PLAN
642	0.07	MILE	EDGE LINE, 6", TYPE 1 (WHITE)
659	2	EACH	SOIL ANALYSIS TEST
659	405	CU. YD.	TOPSOIL
659	3653	SQ. YD.	SEEDING AND MULCHING, CLASS 2
659	0.51	TON	COMMERCIAL FERTILIZER
659	20	MGALLON	WATER
670	3653	SQ. YD.	SLOPE EROSION PROTECTION MAT, TYPE A
832	10,000	EACH	EROSION CONTROL
832	LUMP		STORM WATER POLLUTION PREVENTION PLAN
SPECIAL	2	EACH	12" PRECAST CONCRETE END SECTION
SPECIAL	0.07	MILE	SONIC NAP ALERT PROTECTION (SNAP) 1
SP 614ZP	2,160	HOURS	ZONE PERSON

DESIGN AGENCY
ms consultants, inc.
333 E. Federal Street
Youngstown, Ohio 44503

NO	REVISIONS	BY	DATE
1	ADDENDUM NO. 2	JDK	4/12/23
-	-	-	-
-	-	-	-

DESIGNED	CHECKED	NO
JSP	WER	1
DRAWN	IN CHARGE	-
JSP	JDH	-

GENERAL SUMMARY

WOOD COUNTY

MP 63.6 EB SLOPE REPAIR

PROJECT 70-23-01

DATE: 2/23/23

16
22

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

99-20-04_GENSUM.dwg: 4/12/23 - 8:33am