OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION

ADDENDUM NO. 5
ISSUED OCTOBER 5, 2020

to

PROJECT NO. 43-20-03
BRIDGE DECK REPAIR AND REHABILITATION
OHIO TURNPIKE OVER TURNER ROAD (C.R. 103) M.P. 222.7,
OHIO TURNPIKE OVER KIRK ROAD (C.R. 146) M.P. 222.8
MAHONING COUNTY, OHIO

OPENING DATE PREVIOUSLY EXTENDED TO: 2:00 P.M. (EASTERN TIME**), OCTOBER ~~6~~ ~~7~~ 8, 2020**

ATTENTION OF BIDDERS IS DIRECTED TO:
ANSWERS TO QUESTIONS RECEIVED THROUGH 11:00 AM ON OCTOBER 5, 2020

MODIFICATIONS TO THE CONTRACT DOCUMENTS

Plan Sheets: 13, 21, 22, 23, 24, 37, 39, 40, 48, 70 and 78 of 105.
-AND-
Bid Schedule of Items and Estimated Quantities Worksheet
Ref. Nos. 36, 72, 80, 81 and 102

Issued by the Ohio Turnpike and Infrastructure Commission through Jennifer L. Stueber, Esq., General Counsel.

October 5, 2020

Jennifer L. Stueber, Esq., Date
General Counsel

ANSWERS TO QUESTIONS RECEIVED THROUGH 11:00 A.M. ON OCTOBER 5, 2020:

Q#27 Please verify the quantities for Ref #80 & #81 – Steel Piles, Furnished and Driven. It seems that both quantities are overstated. The driven quantity seems to be the furnish quantity. Please also verify the pile quantities on Page 37.

A#27 The quantities for Reference No. 80, Item 507, STEEL PILES, HP10x42, FURNISHED and Reference No. 81, Item 507, STEEL PILES, HP10x42, DRIVEN have been revised. Plan Sheets 22, 37, 39, 40, 48, 70 and 78 of 105, as well as Reference Nos. 80 and 81 on the Estimated Quantities Worksheet and the Bid Schedule of Items have been revised and are included as part of this Addendum.

Q#29 On plan sheet 3/105 please provide a legend for the existing adjoining sections pavement components including their thickness.

A#29 *The existing adjoining sections are included to show lane and shoulder widths. Since the pavement outside of the project limits is not intended to be disturbed, the components of the pavement are not provided.*

Q#34 Please verify the plan quantity for structural steel. There appears to be a discrepancy of approximately 10%

A#34 The quantity calculations for the structural steel were reviewed and no discrepancies found. The quantity provided for the structural steel is correct.

Q#35 Eastbound and Westbound stations on sheet 13 for Phase 2 Temporary Pavement appear to be flipped. Please clarify.

A#35 The stations on Plan Sheet 13 of 105 were found to be incorrect. The stations have been revised on Plan Sheet 13 of 105 which is included as part of this Addendum.

Q#36 Please provide a bid item for 202 concrete barrier removal and item 622 concrete barrier, type D for Kirk and Turner road between the Eastbound and Westbound Bridges.

A#36 Reference No. 72, Item 622 Concrete Barrier, Single Slope, Type D has been added along Kirk and Turner Road in the roadway plans. Reference No. 36, Item 202, Concrete Barrier Removed and Reference No. 72, Item 622 Concrete Barrier, Single Slope, Type D quantities have also been revised to correct a discrepany and the new totals reflect this as well. Plan Sheets 21, 23 and 24 of 105, the Estimated Quantities Worksheet and the Bid Schedule of Items have been revised to reflect this change and are included as part of this Addendum.

Q#37 Please verify the quantities for Ref #102 – Replace Expansion Bearing Device and Ref #103 – Replace Expansion Bearing Device. Both quantities are understated by 12 each. Please review and revise.

A#37 Reference No. 102, Item SP 516G, Replace Expansion Bearing Device, for MP 222.8 Kirk Road Bridge is incorrect and has been revised to 36 each. No changes for MP 222.7 Turner Road Bridge. Plan Sheets 22 and 39 of 105, the Estimated Quantities Worksheet and the Bid Schedule of Items have been revised to reflect this change and are included as part of this Addendum.

Q#38 Is the median paved gutter required to be replaced to its original line and grade?

A#38 Yes, the gutter is to be replaced to the same line and grade.

Q#39 Plan sheets 15 and 18/105 indicate multiple locations that conduits are to be plugged and filled. Please provide a bid item for this work.

A#39 These items shall be included for payment in Item SP 202, Portions of Structure Removed. An additional bid item will not be added.

Q#40 Plan sheet 15/105 indicates a catch basin to be abandoned as per plan. Please provide a bid item for this work.

A#40 This item shall be included for payment in Item SP 202, Portions of Structure Removed. An additional bid item will not be added.

END OF ADDENDUM NO. 5