



**OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION**

ADDENDUM NO. 8
ISSUED OCTOBER 15, 2020

to

PROJECT NO. 43-20-03
BRIDGE DECK REPAIR AND REHABILITATION
OHIO TURNPIKE OVER TURNER ROAD (C.R. 103) M.P. 222.7,
OHIO TURNPIKE OVER KIRK ROAD (C.R. 146) M.P. 222.8
MAHONING COUNTY, OHIO

OPENING DATE PREVIOUSLY EXTENDED TO: 2:30 P.M. (EASTERN TIME), OCTOBER 20, 2020

ATTENTION OF BIDDERS IS DIRECTED TO:
ANSWERS TO QUESTIONS RECEIVED THROUGH 10:00 AM ON OCTOBER 15, 2020

Issued by the Ohio Turnpike and Infrastructure Commission through Jennifer L. Stueber, Esq., General Counsel.

A handwritten signature in blue ink, appearing to read "JL Stueber", is written over a horizontal line.

Jennifer L. Stueber, Esq.,
General Counsel

October 15, 2020
Date

ANSWERS TO QUESTIONS RECEIVED THROUGH 10:00 A.M. ON OCTOBER 15, 2020:

Q#55 Addendum #7 added the existing diaphragms between phase line beams are to be removed and reinstalled. What, if any, surface prep and painting needs to be done to the faying surfaces on the existing beams and diaphragms prior to reinstallation?

A#55 The connection between the existing beam and diaphragms is not a critical connection therefore the faying surfaces DO NOT need to be cleaned and coated in accordance with paragraph 1.02 of SP 514A, Field Painting of Existing Structures – System OZEU. If during the contractor's operations, the existing faying surfaces are contaminated with rust and/or dirt, then they shall be sufficiently cleaned in order to permit proper fit up. This work, if required, shall be included with Item SP 202, Portions of Structure Removed for payment.

END OF ADDENDUM NO. 8