



**OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION**

ADDENDUM NO. 3
ISSUED FEBRUARY 18, 2021

To

PROJECT NO. 59-21-02
REPAIRS AND RESURFACING
EASTBOUND AND WESTBOUND ROADWAYS
MILEPOST 112.45 TO MILEPOST 118.80
ERIE COUNTY, OHIO

OPENING DATE: 2:00 P.M. (EASTERN TIME), FEBRUARY 23, 2021

ATTENTION OF BIDDERS IS DIRECTED TO:

ANSWERS TO QUESTIONS RECEIVED THROUGH 10:00 AM ON FEBRUARY 18, 2021

Issued by the Ohio Turnpike and Infrastructure Commission through Jennifer L. Stueber, Esq., General Counsel.

Jennifer L. Stueber, Esq.,
General Counsel

February 18, 2021
Date

ANSWERS TO QUESTIONS RECEIVED THROUGH 10:00 A.M. ON FEBRUARY 18, 2021:

Q#11 Regarding OTIC answer to question #7 regarding QC-2 will not be permitted in lieu of Class S Concrete, is there another type of concrete mix that can be used instead of Class S concrete? We cannot find any local concrete suppliers that will produce Class S concrete.

A#11 The response to Q#7 for Addendum No. 2 is revised as follows: For Item Special, Median Wall Repair, the use of QC-1 concrete will be permitted, and for Item 202, Portions of Structure Removed, As Per Plan, the use of QC-2 concrete will be permitted.

Q#12 Please clarify pre bid question and answer in addendum two concerning the requirement of Class S Concrete, for wall replacement in bid item portions of structure removed. Our concrete supplier is requesting the requirements of Class S Concrete. Class S Concrete is not part of this projects contract documents or ODOTS current CMS. Per ODOTS CMS, bridge parapets are to be installed using QC2. Please consider QC2 for this project or provide specifications for Class S Concrete.

A#12 See the response to Q#11.

END OF ADDENDUM NO. 3