

General Info

Number: PROJECT NO. 59-26-07
Description: RESURFACING EASTBOUND AND WESTBOUND ROADWAYS
MILEPOST 221.33 TO MILEPOST 230.35
MAHONING COUNTY, OHIO
Deadline: FEBRUARY 26, 2026 @ 2:00 P.M. (EASTERN TIME)

(Estimated Cost: \$15,500,000.00)

Bids

Business	Bid Total
The Shelly Company - Northeast Division	\$15,452,547.80

THE SHELLY COMPANY NORTHEAST DIVISION
PROJECT NO. 59-26-07 (Ref. Nos. 1-64)

Ref. No.	Item No.	Item Ext.	Item Description	Approx. Quantity	Units	Unit Price	Extension
1	IB. ART.6	100ESP001	PREMIUM FOR CONTRACT PERFORMANCE BOND AND PAYMENT BOND	1.00	LUMP	\$100,000.00	\$100,000.00
2	202	202E32000	CURB REMOVED	8,635.00	FOOT	\$5.00	\$43,175.00
3	202	202E35100	PIPE REMOVED, 24" AND UNDER	700.00	FOOT	\$15.00	\$10,500.00
4	202	202E38000	GUARDRAIL REMOVED	27,613.00	FOOT	\$3.00	\$82,839.00
5	202	202E38101	GUARDRAIL REMOVED FOR STORAGE, AS PER PLAN	500.00	FOOT	\$3.00	\$1,500.00
6	SP 202B	202ESB100	CRACK REPAIR, 1" OR LESS, USING SAND ASPHALT	100.00	CU.YD.	\$200.00	\$20,000.00
7	SP 202B	202ESB101	CRACK REPAIR, 1" OR LESS, USING HOT JOINT SEALER	4,600.00	GALLON	\$6.00	\$27,600.00
8	SP 202B	202ESB102	CRACK REPAIR, WIDER THAN 1" AND LESS THAN 1" IN DEPTH, USING SP 404 (PG 64-22)	100.00	CU.YD.	\$200.00	\$20,000.00
9	SP 202B	202ESB103	CRACK REPAIR, WIDER THAN 1" AND GREATER THAN 1" IN DEPTH, USING SP 402 (PG 64-22)	100.00	CU.YD.	\$200.00	\$20,000.00
10	SP 202B	202ESB104	3 CORNER CRACK REPAIR, USING SP 402 (PG 64-22)	100.00	CU. YD.	\$300.00	\$30,000.00
11	SP 202B	202ESB105	REPAIR OF EXISTING EXPANSION JOINT, USING SP 404 (PG 64-22)	65.00	CU.YD.	\$200.00	\$13,000.00
12	209	209E60501	LINEAR GRADING, AS PER PLAN	24.20	MILE	\$3,200.00	\$77,440.00
13	254	254E01000	PAVEMENT PLANING, ASPHALT CONCRETE, 1.25"	177,159.00	SQ.YD.	\$2.10	\$372,033.90
14	254	254E01000	PAVEMENT PLANING, ASPHALT CONCRETE, 1.5"	382.00	SQ.YD.	\$3.00	\$1,146.00
15	254	254E01000	PAVEMENT PLANING, ASPHALT CONCRETE, 3"	269,305.00	SQ.YD.	\$2.35	\$632,866.75
16	254	254E01010	PAVEMENT PLANING, PORTLAND CEMENT CONCRETE, 1.5"	265.00	SQ.YD.	\$4.00	\$1,060.00
17	254	254E01011	PAVEMENT PLANING, PORTLAND CEMENT CONCRETE, AS PER PLAN	512.00	SQ.YD.	\$50.00	\$25,600.00
18	SP 402	402ES1005	ASPHALT CONCRETE INTERMEDIATE COURSE, PG 64-22	360.00	CU.YD.	\$280.00	\$100,800.00
19	SP 402	402ES1003	ASPHALT CONCRETE INTERMEDIATE COURSE, USING CRUSHED STONE, PG 76-22(FR)	13,097.00	CU.YD.	\$240.00	\$3,143,280.00
20	SP 404	404ES1001	ASPHALT CONCRETE SURFACE COURSE, USING CRUSHED STONE, PG 64-22	360.00	CU.YD.	\$340.00	\$122,400.00
21	SP 404	404ES1SL2	ASPHALT CONCRETE SURFACE COURSE, USING CRUSHED SLAG, PG 76-22 (FR)	15,493.00	CU.YD.	\$280.00	\$4,338,040.00
22	SP 404A	404ESA100	JOINT SEALER	187,901.00	FOOT	\$0.65	\$122,135.65
23	407	407E20000	NON-TRACKING TACK COAT	57,550.00	GALLON	\$3.00	\$172,650.00
24	606	606E15101	GUARDRAIL, TYPE MGS, WITH LONG POSTS, AS PER PLAN	24,800.00	FOOT	\$24.50	\$607,600.00
25	606	606E26551	ANCHOR ASSEMBLY, MGS TYPE T, AS PER PLAN	18.00	EACH	\$1,375.00	\$24,750.00
26	SP 606A	606ESAGR2	ANCHOR ASSEMBLY, MGS TYPE E	33.00	EACH	\$2,500.00	\$82,500.00
27	606	606E35003	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1, AS PER PLAN	31.00	EACH	\$2,500.00	\$77,500.00
28	606	606E35102	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 2	9.00	EACH	\$625.00	\$5,625.00
29	609	609E10000	ASPHALT CONCRETE CURB, TYPE 1	8,635.00	FOOT	\$12.90	\$111,391.50
30	611	611E05200	12" CONDUIT, TYPE F, 707.33	700.00	FOOT	\$40.00	\$28,000.00
31	SP 611	611ESCBR1	CATCH BASIN RECONSTRUCTED TO GRADE, LESS THAN 4", AS PER PLAN	5.00	EACH	\$2,000.00	\$10,000.00
32	SP 611	611ESCBR2	CATCH BASIN RECONSTRUCTED TO GRADE, 4" - 12", AS PER PLAN	14.00	EACH	\$3,000.00	\$42,000.00
33	SP 611	611ESCBR3	CATCH BASIN RECONSTRUCTED TO GRADE, GREATER THAN 12", AS PER PLAN	5.00	EACH	\$4,000.00	\$20,000.00
34	SP 611	611ESGCA1	CATCH BASIN, GRATE AND CASTING, AS PER PLAN	14.00	EACH	\$1,200.00	\$16,800.00
35	SP 614	614ESMOT2	MAINTAINING TRAFFIC, AS PER PLAN	1.00	LUMP	\$2,027,500.00	\$2,027,500.00
36	614	614E11110	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	2,436.00	HOURS	\$100.00	\$243,600.00
37	614	614E13001	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC, AS PER PLAN	10.00	CU.YD.	\$125.00	\$1,250.00
38	614	614E20110	WORK ZONE LANE LINE, CLASS I, 6", 642 PAINT	19.00	MILE	\$1,500.00	\$28,500.00
39	614	614E22110	WORK ZONE EDGE LINE, CLASS I, 6", 642 PAINT	37.00	MILE	\$1,200.00	\$44,400.00
40	617	617E20000	SHOULDER PREPARATION	56,678.00	SQ.YD.	\$2.00	\$113,356.00
41	617	617E10100	COMPACTED AGGREGATE	4,750.00	CU.YD.	\$130.00	\$617,500.00
42	617	617E25000	WATER	50.00	MGAL	\$15.00	\$750.00
43	619	619E16010	FIELD OFFICE, TYPE B	16.00	MONTH	\$4,000.00	\$64,000.00
44	621	621E54000	RAISED PAVEMENT MARKER REMOVED	1,192.00	EACH	\$8.00	\$9,536.00
45	SP 621	621ES0101	RAISED PAVEMENT MARKER	1,192.00	EACH	\$36.75	\$43,806.00
46	SP 623	623ES0100	CONSTRUCTION LAYOUT SURVEY	1.00	LUMP	\$30,000.00	\$30,000.00
47	624	624E10000	MOBILIZATION	1.00	LUMP	\$400,000.00	\$400,000.00
48	626	626E00110	BARRIER REFLECTOR, TYPE 2, ONE WAY	312.00	EACH	\$15.00	\$4,680.00
49	SP 627	627ES0102	STONE SHOULDER PROTECTION	1,023.00	CU.YD.	\$155.00	\$158,565.00
50	642	642E00104	EDGE LINE, 6", TYPE 1	60.40	MILE	\$1,025.00	\$61,910.00
51	642	642E00204	LANE LINE, 6", TYPE 1	30.20	MILE	\$750.00	\$22,650.00
52	SP 808	808ESDLS1	DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY	90.00	SIGN MONTH	\$675.00	\$60,750.00
53	872	872E10001	VOID REDUCING ASPHALT MEMBRANE (VRAM), AS PER PLAN	93,351.00	FOOT	\$2.00	\$186,702.00
54	SPECIAL	990ETP008	AIR SPEED ZONE MARKINGS, AS PER PLAN	10.00	EACH	\$946.00	\$9,460.00
55	SPECIAL	990ETP010	REGRADING UNDER GUARDRAIL	26,300.00	SQ.YD.	\$1.00	\$26,300.00
56	SPECIAL	990ETP005	SONIC NAP ALERT PATTERN (SNAP)	36.00	MILE	\$775.00	\$27,900.00
57	SPECIAL	990ETP023	EXISTING AGGREGATE DRAIN CLEANOUT	10,200.00	SQ. YD.	\$50.00	\$510,000.00

58	SPECIAL	990ETP009	PATCHING CONCRETE BRIDGE DECKS, TYPE B	100.00	SQ.YD.	\$1,200.00	\$120,000.00
59	SPECIAL	990ETP018	DIGITAL SPEED LIMIT (DSL) WITH DIGITAL VEHICLE SPEED FEEDBACK SIGN ASSEMBLY PROCUREMENT	2.00	EACH	\$13,500.00	\$27,000.00
60	SPECIAL	990ETP025	DIGITAL SPEED LIMIT (DSL) WITH DIGITAL VEHICLE SPEED FEEDBACK SIGN ASSEMBLY OPERATION	18.00	SIGN MONTH	\$350.00	\$6,300.00
61	204	204E13000	EXCAVATION OF SUBGRADE	200.00	CU. YD.	\$30.00	\$6,000.00
62	204	204E20000	EMBANKMENT	100.00	CU. YD.	\$150.00	\$15,000.00
63	204	204E10000	SUBGRADE COMPACTION	300.00	SQ. YD.	\$3.00	\$900.00
64	SP 451	451ES100A	FULL DEPTH PAVEMENT REPAIRS (ASPHALT)	320.00	SQ. YD.	\$250.00	\$80,000.00

Total: \$15,452,547.80

TOTAL BID AMOUNT (REF. NO. 1 THRU REF. NO. 64) ----- \$15,452,547.80