

General Info

Number: PROJECT NO. 43-27-03 REBID
Description: BRIDGE REPLACEMENT AND BRIDGE REHABILITATION
NETTLE CREEK ROAD BRIDGE (CR N.30) OVER THE OHIO TURNPIKE MAINLINE AT MILEPOST 6.0,
WHITE BRIDGE ROAD BRIDGE (CR 7.75) OVER THE OHIO TURNPIKE MAINLINE AT MILEPOST 6.9,
AND CHAMPION ROAD BRIDGE (CR 8.50) OVER THE OHIO TURNPIKE MAINLINE AT MILEPOST 7.7
WILLIAMS COUNTY, OHIO
Deadline: OCTOBER 1, 2026 @ 2:00 P.M. (EASTERN TIME)

(Estimated Cost: \$12,000,000.00)

Bids**Business****Bid Total**

Miller Bros. Const., Inc.

\$13,447,863.84

ROADWAY (Ref. Nos. 1 - 23)

Total: \$235.903.78

Ref. No.	Item No.	Item Ext.	Item Description
----------	----------	-----------	------------------

Total: \$59,107.65

Ref. No.	Item No.	Item Ext.	Item Description
----------	----------	-----------	------------------

Total: \$69,021.59

PAVEMENT (Ref. Nos. 41 - 49)

Ref. No.	Item No.	Item Ext.	Item Description	Approx. Quantity	Units	Unit Price	Extension
41	254	254E01000	PAVEMENT PLANING, ASPHALT CONCRETE (T=3")	798.00	SY	\$9.50	\$7,581.00
42	254	254E01000	PAVEMENT PLANING, ASPHALT CONCRETE (T=VARIABLE)	152.00	SY	\$11.00	\$1,672.00
43	302	302E56000	ASPHALT CONCRETE BASE, PG64-22, (449)	204.00	CY	\$320.00	\$65,280.00
44	304	304E20000	AGGREGATE BASE	314.00	CY	\$177.54	\$55,747.56
45	407	407E20000	NON-TRACKING TACK COAT	313.00	GAL	\$1.00	\$313.00
46	441	441E70000	ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (449), PG64-22	86.00	CY	\$420.00	\$36,120.00
47	441	441E70300	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2 (449)	118.00	CY	\$350.00	\$41,300.00
48	609	609E24510	CURB, TYPE 4-C	336.00	FT	\$76.11	\$25,572.96
49	617	617E10100	COMPACTED AGGREGATE	42.00	CY	\$161.41	\$6,779.22
Total:							\$240,365.74

TRAFFIC CONTROL (Ref. Nos. 50 - 63)

Ref. No.	Item No.	Item Ext.	Item Description	Approx. Quantity	Units	Unit Price	Extension
50	SP626	626ESBRT1	BARRIER REFLECTOR, TYPE 1	602.00	EACH	\$12.50	\$7,525.00
51	626	626E00102	BARRIER REFLECTOR, TYPE 1 (BIDIRECTIONAL)	20.00	EACH	\$12.50	\$250.00
52	626	626E00110	BARRIER REFLECTOR, TYPE 2 (ONE-WAY)	8.00	EACH	\$12.50	\$100.00
53	626	626E00110	BARRIER REFLECTOR, TYPE 2 (BIDIRECTIONAL)	22.00	EACH	\$12.50	\$275.00
54	630	630E03100	GROUND MOUNTED SUPPORT, NO. 3 POST	36.00	FT	\$15.00	\$540.00
55	630	630E80100	SIGN, FLAT SHEET	13.00	SF	\$35.00	\$455.00
56	630	630E08600	SIGN POST REFLECTOR	2.00	EACH	\$50.00	\$100.00
57	630	630E84900	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	2.00	EACH	\$25.00	\$50.00
58	630	630E85100	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	2.00	EACH	\$90.00	\$180.00
59	630	630E86002	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	3.00	EACH	\$25.00	\$75.00
60	642	642E00100	EDGE LINE, 4", TYPE 1	0.60	MILE	\$3,000.00	\$1,800.00
61	642	642E00104	EDGE LINE, 6", TYPE 1	40.30	MILE	\$950.00	\$38,285.00
62	642	642E00204	LANE LINE, 6", TYPE 1	20.20	MILE	\$750.00	\$15,150.00
63	642	642E00300	CENTER LINE, TYPE 1	0.30	MILE	\$6,000.00	\$1,800.00
Total:							\$66,585.00

STRUCTURES - M.P. 6.0 (Ref. Nos. 64 - 99)

Ref. No.	Item No.	Item Ext.	Item Description	Approx. Quantity	Units	Unit Price	Extension
64	202	202E11003	STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	1.00	LS	\$518,799.26	\$518,799.26
65	202	202E22900	APPROACH SLAB REMOVED	130.00	SY	\$89.51	\$11,636.30
66	503	503E11100	COFFERDAMS AND EXCAVATION BRACING	1.00	LS	\$249,199.99	\$249,199.99
67	503	503E21300	UNCLASSIFIED EXCAVATION	1.00	LS	\$209,776.12	\$209,776.12
68	505	505E11100	PILE DRIVING EQUIPMENT MOBILIZATION	1.00	LS	\$50,976.04	\$50,976.04
69	507	507E00500	12" CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN	4,375.00	FT	\$26.35	\$115,281.25
70	507	507E00550	12" CAST-IN-PLACE REINFORCED CONCRETE PILES, FURNISHED	4,820.00	FT	\$90.46	\$436,017.20
71	SP 509	509ESG601	EPOXY COATED REINFORCING STEEL, GRADE 60, AS PER PLAN	125,354.00	LB	\$2.10	\$263,243.40
72	509	509E30020	NO. 4 DEFORMED GFRP REINFORCEMENT	7,471.00	FT	\$2.73	\$20,395.83
73	511	511E33500	SEMI-INTEGRAL DIAPHRAGM GUIDE	2.00	EACH	\$4,215.52	\$8,431.04
74	511	511E41010	CLASS QC1 CONCRETE, PIER ABOVE FOOTING	98.00	CY	\$1,867.38	\$183,003.24
75	511	511E43510	CLASS QC1 CONCRETE, ABUTMENT INCLUDING FOOTING	126.00	CY	\$1,069.70	\$134,782.20
76	511	511E46510	CLASS QC1 CONCRETE, FOOTING	81.00	CY	\$1,220.11	\$98,828.91
77	P 511 (QC:	511ESQC31	CLASS QC2 CONCRETE, BRIDGE DECK, AS PER PLAN	286.00	CY	\$1,993.17	\$570,046.62
78	P 511 (QC:	511ESQC32	CLASS QC2 CONCRETE, BRIDGE DECK (PARAPETS), AS PER PLAN	82.00	CY	\$822.41	\$67,437.62
79	512	512E10101	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), AS PER PLAN	784.00	SY	\$39.45	\$30,928.80
80	513	513E10240	STRUCTURAL STEEL MEMBERS, LEVEL 2	275,600.00	LB	\$3.88	\$1,069,328.00
81	513	513E20000	WELDED STUD SHEAR CONNECTORS	4,296.00	EACH	\$4.85	\$20,835.60
82	514	514E00060	FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT	11,900.00	SF	\$13.00	\$154,700.00
83	514	514E00067	FIELD PAINTING STRUCTURAL STEEL, FINISH COAT, AS PER PLAN	11,900.00	SF	\$6.50	\$77,350.00

84	514	514E10000	FINAL INSPECTION REPAIR	6.00	EACH	\$1.00	\$6.00
85	516	516E10010	ARMORLESS PREFORMED JOINT SEAL	81.00	FT	\$61.32	\$4,966.92
86	516	516E13900	2" PREFORMED EXPANSION JOINT FILLER	60.00	SF	\$13.63	\$817.80
87	516	516E14020	SEMI-INTEGRAL ABUTMENT EXPANSION JOINT SEAL	101.00	FT	\$57.46	\$5,803.46
88	516	516E44100	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (2.5"X22.5"X15" WITH 1.47"X23.5"X16" LOAD PLATE)	8.00	EACH	\$3,839.92	\$30,719.36
89	516	516E44100	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (3"X26"X15" WITH 2.375"X27"X16" LOAD PLATE)	4.00	EACH	\$4,380.33	\$17,521.32
90	516	516E44200	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (3.5"X15"X11" WITH 1.5"X16"X12" LOAD PLATE)	8.00	EACH	\$3,719.81	\$29,758.48
91	518	518E21200	POROUS BACKFILL WITH GEOTEXTILE FABRIC	52.00	CY	\$246.38	\$12,811.76
92	518	518E40000	6" PERFORATED CORRUGATED PLASTIC PIPE	100.00	FT	\$14.67	\$1,467.00
93	518	518E40010	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	40.00	FT	\$22.68	\$907.20
94	523	523E20000	DYNAMIC LOAD TESTING	2.00	EACH	\$6,144.07	\$12,288.14
95	526	526E25001	REINFORCED CONCRETE APPROACH SLAB (T=15"), AS PER PLAN	160.00	SY	\$684.16	\$109,465.60
96	526	526E90030	TYPE C INSTALLATION	87.00	FT	\$368.43	\$32,053.41
97	SP 527	527ES0101	PROTECTIVE FALSEWORK, DEBRIS SHIELD, INSPECTION ACCESS, AND TEMPORARY BRACING	1.00	LS	\$229,315.00	\$229,315.00
98	SP 536	536ES1002	CONCRETE WEATHERPROOFING, DECK, ABUTMENT SLABS, AND APPROACH SLABS	1,026.00	SY	\$14.79	\$15,174.54
99	601	601E20000	CRUSHED AGGREGATE SLOPE PROTECTION	355.00	SY	\$75.60	\$26,838.00
Total:							\$4,820,911.41

STRUCTURES - M.P. 6.9 (Ref. Nos. 100 - 130)

Ref. No.	Item No.	Item Ext.	Item Description	Approx. Quantity	Units	Unit Price	Extension
100	SP 202	202ESPOS	PORTIONS OF STRUCTURE REMOVED	1.00	LS	\$293,100.98	\$293,100.98
101	203	203E35110	GRANULAR MATERIAL, TYPE B	15.00	CY	\$190.40	\$2,856.00
102	509	509E20001	CONCRETE REINFORCEMENT, REPLACEMENT OF EXISTING CONCRETE REINFORCEMENT, AS PER PLAN	100.00	LB	\$4.24	\$424.00
103	SP 509	509ESG601	EPOXY COATED REINFORCING STEEL, GRADE 60, AS PER PLAN	60,975.00	LB	\$2.12	\$129,267.00
104	509	509E30020	NO. 4 DEFORMED GFRP REINFORCEMENT	6,179.00	FT	\$2.58	\$15,941.82
105	510	510E10000	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT	340.00	EACH	\$40.74	\$13,851.60
106	5P 511(QC2	511ESQC21	CLASS QC2 CONCRETE, BRIDGE DECK	162.00	CY	\$2,242.26	\$363,246.12
107	5P 511(QC2	511ESQC32	CLASS QC2 CONCRETE, BRIDGE DECK (PARAPETS), AS PER PLAN	65.00	CY	\$1,508.09	\$98,025.85
108	5P 511(QC2	511ESQC23	CLASS QC2 CONCRETE, ABUTMENT SLAB	32.00	CY	\$1,690.31	\$54,089.92
109	512	512E10101	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), AS PER PLAN	833.00	SY	\$44.82	\$37,335.06
110	513	513E10240	STRUCTURAL STEEL MEMBERS, LEVEL 2	128,700.00	LB	\$4.14	\$532,818.00
111	513	513E20000	WELDED STUD SHEAR CONNECTORS	3,370.00	EACH	\$4.85	\$16,344.50
112	514	514E00050	SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	2,500.00	SF	\$35.00	\$87,500.00
113	514	514E00056	FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME COAT	2,500.00	SF	\$17.00	\$42,500.00
114	514	514E00060	FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT	9,200.00	SF	\$10.00	\$92,000.00
115	514	514E00067	FIELD PAINTING STRUCTURAL STEEL, FINISH COAT, AS PER PLAN	9,200.00	SF	\$6.75	\$62,100.00
116	514	514E00504	GRINDING FINIS, TEARS, SLIVERS ON EXISTING STRUCTURAL STEEL	10.00	MNHR	\$150.00	\$1,500.00
117	514	514E10000	FINAL INSPECTION REPAIR	10.00	EACH	\$250.00	\$2,500.00
118	516	516E44000	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (1.75"X13"X6.5" WITH 1.5"X24"X7.5" LOAD PLATE)	10.00	EACH	\$3,485.44	\$34,854.40
119	516	516E44000	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (1.75"X12"X7.5" WITH 1.5"X14"X12" LOAD PLATE)	10.00	EACH	\$2,582.78	\$25,827.80
120	516	516E44000	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (1.75"X16"X12" WITH 1.5"X24"X14" LOAD PLATE)	5.00	EACH	\$3,975.22	\$19,876.10
121	516	516E47001	JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN	1.00	LS	\$47,310.93	\$47,310.93
122	SP 516A	516ESA001	CRACK REPAIR USING EPOXY INJECTION	8.00	FT	\$494.93	\$3,959.44
123	SP 519	519ES0100	PATCHING CONCRETE STRUCTURES	61.00	SF	\$404.57	\$24,678.77
124	SP 527	527ES0101	PROTECTIVE FALSEWORK, DEBRIS SHIELD, INSPECTION ACCESS AND TEMPORARY BRACING	1.00	LS	\$168,368.91	\$168,368.91
125	SP 533	533ES0030	3 INCH CONTINUOUS STRIP SEAL IN STRUCTURAL STEEL JOINT	58.00	FT	\$972.64	\$56,413.12
126	SP 533A	533ESA015	1 1/2 INCH ELASTOMERIC COMPRESSION SEAL IN STRUCTURAL STEEL JOINTS	58.00	FT	\$968.45	\$56,170.10
127	SP 536	536ES1002	CONCRETE WEATHERPROOFING, DECK, ABUTMENT SLABS, AND APPROACH SLABS	637.00	SY	\$13.16	\$8,382.92
128	601	601E20000	CRUSHED AGGREGATE SLOPE PROTECTION	202.00	SY	\$77.91	\$15,737.82
129	SP 607	607ESF002	TYPE II FENCE, ALL ALUMINUM (6'-0" CHAIN LINK WITH SPECIALS)	419.00	FT	\$221.00	\$92,599.00
130	625	625E33000	STRUCTURE GROUNDING SYSTEM	1.00	EACH	\$28,500.00	\$28,500.00
Total:							\$2,428,080.16

STRUCTURES - M.P. 7.7 (Ref. Nos. 131-166)

Ref. No.	Item No.	Item Ext.	Item Description	Approx. Quantity	Units	Unit Price	Extension
----------	----------	-----------	------------------	------------------	-------	------------	-----------

131	SP 202	202ESPOS	PORTIONS OF STRUCTURE REMOVED	1.00	LS	\$302,628.08	\$302,628.08
132	203	203E35110	GRANULAR MATERIAL, TYPE B	32.00	CY	\$183.74	\$5,879.68
133	SP 509	509ESG601	EPOXY COATED REINFORCING STEEL, GRADE 60, AS PER PLAN	65,069.00	LB	\$2.10	\$136,644.90
134	509	509E20001	CONCRETE REINFORCEMENT, REPLACEMENT OF EXISTING CONCRETE REINFORCEMENT, AS PER PLAN	100.00	LB	\$4.24	\$424.00
135	509	509E30020	NO. 4 DEFORMED GFRP REINFORCEMENT	5,859.00	FT	\$2.60	\$15,233.40
136	510	510E10000	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT	384.00	EACH	\$41.33	\$15,870.72
137	P 511 (QC;	511ESQC21	CLASS QC2 CONCRETE, BRIDGE DECK	171.00	CY	\$2,152.29	\$368,041.59
138	P 511 (QC;	511ESQC32	CLASS QC2 CONCRETE, BRIDGE DECK (PARAPETS), AS PER PLAN	64.00	CY	\$1,525.71	\$97,645.44
139	P 511 (QC;	511ESQC23	CLASS QC2 CONCRETE, ABUTMENT SLAB	38.00	CY	\$1,374.19	\$52,219.22
140	511	511E42510	CLASS QC1 CONCRETE, PIER CAP	2.00	CY	\$2,942.59	\$5,885.18
141	511	511E44110	CLASS QC1 CONCRETE, ABUTMENT NOT INCLUDING FOOTING	1.00	CY	\$5,400.82	\$5,400.82
142	512	512E10101	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), AS PER PLAN	620.00	SY	\$47.58	\$29,499.60
143	513	513E10240	STRUCTURAL STEEL MEMBERS, LEVEL 2	142,000.00	LB	\$3.87	\$549,540.00
144	513	513E20000	WELDED STUD SHEAR CONNECTORS	3,750.00	EACH	\$4.85	\$18,187.50
145	514	514E00050	SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	2,300.00	SF	\$36.00	\$82,800.00
146	514	514E00056	FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME COAT	2,300.00	SF	\$17.00	\$39,100.00
147	514	514E00060	FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT	8,000.00	SF	\$10.00	\$80,000.00
148	514	514E00067	FIELD PAINTING STRUCTURAL STEEL, FINISH COAT, AS PER PLAN	8,000.00	SF	\$7.10	\$56,800.00
149	514	514E00504	GRINDING FINS, TEARS, SLIVERS ON EXISTING STRUCTURAL STEEL	10.00	MNHR	\$150.00	\$1,500.00
150	514	514E10000	FINAL INSPECTION REPAIR	10.00	EACH	\$250.00	\$2,500.00
151	516	516E44200	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (2.109" x 12"x 12" WITH 1.5" x 26" x 13" LOAD PLATE)	4.00	EACH	\$5,403.56	\$21,614.24
152	516	516E44300	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (2.359" x 12"x 12" WITH 1.5" x 26" x 13" LOAD PLATE AN	6.00	EACH	\$6,030.87	\$36,185.22
153	516	516E44200	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (2.109"x 12"x 12" WITH 1.5" x 14.5" x 13" BEVELED LOAC	4.00	EACH	\$5,833.34	\$23,333.36
154	516	516E44300	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (2.359" x 12"x 12" WITH 1.5" x 26" x 13" BEVELED LOAD	6.00	EACH	\$6,094.14	\$36,564.84
155	516	516E44200	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (2.359" x 12"x 12" WITH 1.5" x 17" x 13" BEVELED LOAD	10.00	EACH	\$5,848.79	\$58,487.90
156	516	516E44200	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (2.728" x 15"x 15" WITH 1.5" x 27" x 16" LOAD PLATE)	5.00	EACH	\$5,469.61	\$27,348.05
157	516	516E47001	JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN	1.00	LS	\$52,076.25	\$52,076.25
158	SP 516A	516ESA001	CRACK REPAIR BY EPOXY INJECTION	15.00	FT	\$293.91	\$4,408.65
159	SP 519	519ES0100	PATCHING OF CONCRETE STRUCTURES	52.00	SF	\$419.33	\$21,805.16
160	SP 527	527ES0101	PROTECTIVE FALSEWORK, DEBRIS SHIELD, INSPECTION ACCESS AND TEMPORARY BRACING	1.00	LS	\$222,700.18	\$222,700.18
161	SP 533	533ES0030	3 INCH CONTINUOUS STRIP SEAL IN STRUCTURAL STEEL JOINT	62.00	FT	\$986.50	\$61,163.00
162	SP 533A	533ESA015	1 1/2 INCH ELASTOMERIC COMPRESSION SEAL IN STRUCTURAL STEEL JOINTS	62.00	FT	\$963.44	\$59,733.28
163	SP 536	536ES1002	CONCRETE WEATHERPROOFING, DECK, ABUTMENT SLABS, AND APPROACH SLABS	900.00	SY	\$15.02	\$13,518.00
164	601	601E20000	CRUSHED AGGREGATE SLOPE PROTECTION	227.00	SY	\$79.41	\$18,026.07
165	SP 607	607ESF002	TYPE II FENCE, ALL ALUMINUM (6'-0" CHAIN LINK WITH SPECIALS)	412.00	FT	\$221.00	\$91,052.00
166	625	625E33000	STRUCTURE GROUNDING SYSTEM	1.00	EACH	\$29,500.00	\$29,500.00

Total: \$2,643,316.33

MAINTENANCE OF TRAFFIC (Ref. Nos. 167-172)

Ref. No.	Item No.	Item Ext.	Item Description	Approx. Quantity	Units	Unit Price	Extension
167	614	614E11111	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE, AS PER PLAN	40.00	HOURL	\$129.75	\$5,190.00
168	614	614E12381	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (UNIDIRECTIONAL), AS PER PLAN	8.00	EACH	\$2,100.00	\$16,800.00
169	614	614E12420	DETOUR SIGNING	1.00	LS	\$15,000.00	\$15,000.00
170	614	614E13350	OBJECT MARKER, ONE-WAY	120.00	EACH	\$20.00	\$2,400.00
171	614	614E18010	MAINTAINING TRAFFIC, MISC.: ADDITIONAL SIGNS WITH SUPPORTS	128.00	SF	\$25.00	\$3,200.00
172	622	622E41101	PORTABLE BARRIER, UNANCHORED, AS PER PLAN	6,000.00	FT	\$53.17	\$319,020.00

Total: \$361,610.00

GENERAL (Ref. Nos. 173-177)

Ref. No.	Item No.	Item Ext.	Item Description	Approx. Quantity	Units	Unit Price	Extension
173	IB.ART.6	100ESP001	PREMIUM FOR CONTRACT PERFORMANCE BOND AND PAYMENT BOND	1.00	LS	\$49,528.48	\$49,528.48
174	SP 614	614ESMOT1	MAINTAINING TRAFFIC	1.00	LS	\$1,702,519.91	\$1,702,519.91
175	SP 619	619ESFOMB	FIELD OFFICE, TYPE B	20.00	MONTH	\$4,020.53	\$80,410.60
176	SP 623	623ES0100	CONSTRUCTION LAYOUT SURVEY	1.00	LS	\$18,110.00	\$18,110.00
177	624	624E10000	MOBILIZATION	1.00	LS	\$672,393.19	\$672,393.19

Total: \$2,522,962.18

TOTAL BID AMOUNT (REF. NO. 1 THRU REF. NO. 177) -----

\$13,447,863.84