

TCB-3 2017.10.20.dwg; 10/25/17 - 4:42pm



NOTES:

1. CONTRACTOR SHALL ALIGN EXISTING CONCRETE PORTABLE BARRIER ALONG Ø OF TURNPIKE.
2. CONTRACTOR TO FIELD VERIFY HEIGHT, WIDTH AND OPENING OF EXISTING CONCRETE PORTABLE BARRIER AFTER REALIGNMENT.
3. CONTRACTOR SHALL INSTALL ADDITIONAL SECTIONS OF CONCRETE PORTABLE BARRIER (MINIMUM 2) IN THE GAP TO END UP WITH A CLOSURE PIECE WITH A LENGTH THAT IS LESS THAN 10 FEET. THE REMAINING GAP SHALL BE CLOSED IN ACCORDANCE WITH NOTE 4.
4. THE CONTRACTOR SHALL FIELD VERIFY THE LENGTH AND HEIGHT REQUIRED FOR THE CLOSURE PIECE. A CLOSURE PIECE CAN BE EITHER CAST IN PLACE IN ACCORDANCE WITH ITEM 622 OR A PIECE OF EXISTING BARRIER THAT HAS BEEN SIZED TO MATCH THE NEEDED CLOSURE WIDTH. IF CAST IN PLACE IS UTILIZED, A BOND BREAKER SHALL BE USED UNDER THE CLOSURE PIECE SO AS TO NOT DISCOLOR OR DAMAGE THE EXISTING ASPHALT. IF A SIZED PIECE OF EXISTING BARRIER IS USED, THE CUT END SHALL HAVE A SMOOTH FACE AND THE APPROPRIATE CONNECTIONS SHALL BE DRILLED AND GROUTED INTO THE BARRIER PER THE DIMENSIONS AS SHOWN ON ODOT STANDARD CONSTRUCTION DRAWING RM-4.2. GROUT USED FOR ANCHORING OF CONNECTIONS SHALL BE IN ACCORDANCE WITH 705.20.
5. THE CONTRACTOR SHALL REMOVE THE ITEMS INSTALLED FOR GAP CLOSURE AFTER COMPLETION OF ALL WORK WITHIN THE ZONE AND RESTORE THE CONCRETE PORTABLE BARRIER IN ACCORDANCE WITH OTIC STANDARD DRAWING XV-3 OR AS DIRECTED BY THE CHIEF ENGINEER.
6. PAYMENT FOR ALL EQUIPMENT, MATERIALS, LABOR AND INCIDENTALS NECESSARY TO CLOSE AND RE-OPEN THE MEDIAN BARRIER WALL SHALL BE INCLUDED IN THE LUMP SUM BID PRICE FOR ITEM SPECIAL - EXISTING CROSSOVER TO BE CLOSED/RE-OPENED.
7. ALL MATERIALS PROVIDED FOR THIS WORK SHALL BE IN ACCORDANCE WITH ODOT STANDARD CONSTRUCTION DRAWING RM-4.2 AND ITEM 622.

DATE: OCTOBER 20, 2017

STANDARD DRAWING

MEDIAN BARRIER WALL
CLOSURE DETAILS

TCB-3

1 / 1



OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

